

Upper Deer Creek Regional Stormwater Facility

Effectiveness Study
2006 - 2010



Dana Morton & Greg McGrath



CDM

Features

- ◆ Retrofit treatment for 516 acres of tributary area
 - ◆ Untreated downtown industrial/residential area
 - ◆ Over 70% impervious
- ◆ Compensatory treatment via expansion planned for new Jacksonville Courthouse and Library
- ◆ 7 acre facility provides flood control
- ◆ Adjacent brownfield site requires a hydraulic barrier to keep groundwater pollution isolated
- ◆ Performance monitoring

City of Jacksonville NPDES/MS4 Permit

STATE OF FLORIDA MUNICIPAL SEPARATE STORM SEWER SYSTEM PERMIT

PERMIT NUMBER: FLS000012 Major Facility

ISSUANCE DATE: October 8, 2002

EXPIRATION DATE: October 7, 2007

City of Jacksonville MS4– Municipal Separate Storm Sewer System Permittee(s):

CO-PERMITTEE(S):

City of Jacksonville
220 East Bay Street
Jacksonville, Florida 32202

City of Atlantic Beach
1200 Sandpiper Lane
Atlantic Beach, Florida 32233-5834

Florida Department of Transportation – District Two
1109 South Marion Street
Lake City, Florida 32025-5874

City of Neptune Beach
116 First Street
Neptune Beach, Florida 32266-6140

Phase I MS4 Monitoring Plans must meet the following goals:

1. **Identify** potential water quality problem areas related to stormwater runoff that can be targeted for corrective action.
2. Measure the **effectiveness** of stormwater pollution reduction measures (i.e., BMPs) that have been or will be implemented; and
3. Document pollutant **loadings and/or trends** in pollutant loadings for specific watersheds or outfalls.

Monitoring Plan

- ◆ Seven storm events (0.2 – 1.5 inches)
 - ◆ Three dry season (October 1 through April 30)
 - ◆ Four wet season (May 1 through September 30)
- ◆ Inflow location center of 72 inch inlet pipe designated “UDC1”
- ◆ Outflow location 24 inch discharge pipe designated “UDC2”



Monitoring Plan Constituents


Flow weighted composite:

- ◆ NH₃, TKN, NO₂
- ◆ TP, OP
- ◆ TSS
- ◆ Cd, Cr, Cu, Zn

Grab:

- ◆ Oil & Grease
- ◆ Fecal coliform bacteria






**Under construction
2006**



**72 inch ID Inlet Structure
2006**



**John Abendroth, Silvia Costin,
Dana Morton & Patrick Victor
2006**



**Dana Morton & Patrick Victor
2006**



**Under construction
2006**






**Under construction
2006**



Hydraulic Barrier

- ◆ Groundwater modeling to characterize transport of contaminants from adjacent brownfields site (MODFLOW).
- ◆ Small trench surrounds RSF on elevated grade;
- ◆ Constant head applied above water level of pond:
 - ◆ Maintained by 500 GPM pump
 - ◆ Constant circulation of water from pond, up into trench, and down soil column isolates contaminants (a 'curtain' of water)







July 2009



**UDC 1 sampling site under construction
2007**








5 gallon
glass
sample
container



Performance Monitoring at Intake


ISCO 750 Area Velocity Meter
ISCO 6712 Auto-Sampler























Ants!!!



Ants!!!








← Rainfall


← Inflow

← Stage

Nitrogen Event Mean Concentrations (mg/L) Mean for Six Storms



Mass Loadings and Removal in pounds For six storms during study period



Comparison of Expected Removal Efficiencies

Constituent	Published Expected Removal Efficiency (%)	UDC Estimated Removal Efficiency (%)
Total Nitrogen	37	37
Orthophosphate as P	79	27
Phosphorus-Total	69	81
Total Suspended Solids	77	91
Copper	69	82
Zinc	85	94

Construction for expansion to begin this year 5.5 to 12.3 acres.





Beemat Evaluation

July 2010



Building a Beemat



Beemat Evaluation

July 2010