SUBJECT: PEDESTRIAN SAFETY IMPROVEMENT PROGRAM – NORTH, WEST, SOUTHEAST AREAS – RE-BID

BID #: CP-0035-24 **OPEN DATE:** 4/17/2024

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT: CONSTRUCTION CONTRACT – DATE OF EXECUTED CONTRACT THROUGH SEPTEMBER 30, 2024 WITH TWO (2) ONE (1) YEAR RENEWAL OPTIONS

AGENCY: RIGHT OF WAY AND STORMWATER MAINTENANCE DIVISION

BASIS OF AWARD: ALL OR NONE TO THE LOWEST RESPONSIVE, RESPONSIBLE BIDDER

NUMBER OF BIDS INVITED: 10 **NUMBER RECEIVED:** 3 **OTHER:** 0

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:
Recommend approval of award to the lowest responsive, responsible bidder, GEC Trucking & Construction, Inc., in the initial not-to-exceed award amount of $548,880.00 per area ($1,646,640.00 total). Period of service will be from the date of executed contract through September 30, 2024 with two (2) one-year renewal options.

This award will be funded from various Right of Way and Stormwater Maintenance Division accounts, executed by formal contract through the Office of General Counsel, and processed via individual Purchase Orders.

ATTACHMENTS: Recommendation Letters, EBO Letter, Bid Tabulation, Basis of Award, Scope of Work

ANALYST: _____
DAVID KLAGES

RESPECTFULLY SUBMITTED: _____
DUSTIN FREEMAN, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: JAMES CARROLL, CHIEF, RIGHT OF WAY AND STORMWATER MAINTENANCE DIVISION

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING _____ MEMBERS DISAPPROVING _____ DATE: _____

_____ _____ OTHER: _____

_____ _____

_____ _____

ACTION OF AWARDING AUTHORITY DATE _____

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

DocuSign Envelope ID: 762B5443-40B3-4E90-A9CC-5481DE2235EC

ONE CITY. ONE JACKSONVILLE.

City of Jacksonville, Florida

Donna Deegan, Mayor

Department of Public Works
Right of Way & Stormwater Maintenance Division
609 St. Johns Bluff Road
Jacksonville, FL 32225
(904) 472-2900
Jacksonville.gov

May 1, 2024

M E M O R A N D U M

TO: **Dustin L. Freeman**
Chief of Procurement Division

THRU: **Nina Sickler, P.E., Director**
Public Works Division

DocuSigned by: Nina Sickler
1EFA223D5D23497...

FROM: **James Carroll, Chief**
Right-of-Way and Stormwater Maintenance Division

DocuSigned by: James Carroll
6CE565F6134A4...

SUBJECT: **Recommendation to Award, CP-0035-24**
GEC Trucking & Construction, Inc.
Pedestrian Safety Improvement Program - North, West and Southeast Areas

---

The Right of Way and Stormwater Maintenance Division of the Department of Public Works have received and reviewed the bid submittals on the referenced project for compliance with the contract documents.

The lowest qualified bids submitted by GEC Trucking & Construction, Inc. comply with the contract documents as required and should be accepted.

We therefore recommend the Pedestrian Safety Improvement Program – North, West & Southeast Area contracts, be awarded to GEC Trucking & Construction, Inc., 5855 Richard Street Jacksonville, Florida 32216, for a not to exceed limit of $548,880.00 for each area. Period will be from Date of Award for all three (3) CONTRACTS THROUGH September 30, 2024, with the two (2), one (1) year renewal options. Work to be performed under individual PO's will be issued for each project. Funding is to be allocated through the FY 23/24 budget.

Should additional information be needed, please contact Amy Griffin at 904-255-6927.

AG

ONE CITY ONE JACKSONVILLE

Countywide Program Management Services for Resurfacing & New Sidewalk Construction

May 1, 2024

Ms. Amy Griffin
City of Jacksonville
Right of Way / Stormwater Maintenance
609 St. Johns Bluff Road North
Jacksonville, FL 32225

Re: Pedestrian Safety Improvement Program – North, West and Southeast Areas;
Re- Bid No.: CP-0007-24
E&R City Contract # 71491-22; E&R Project # 2464-a; PO #: 650044-23

Dear Ms. Griffin:

EISMAN & RUSSO (E&R) has reviewed the three (3) re-bids submitted for the Pedestrian Safety Improvement Program – North, West and Southeast Areas; Bid No.: CP-0035-24

After review, E&R recognized that the Apparent Low Bidder (GEC Trucking & Construction, Inc.) submitted a bid that was significantly lower than the other two Bidders. Therefore, in an effort to confirm that there was no error by the Apparent Low Bidder, Eisman & Russo contacted the owner (Gene Carter, Sr.). Mr. Carter Sr. stated that he was comfortable with both the project scope and bid values that were included in the GEC Trucking & Construction, Inc. bid proposal. Consequently, E&R recommends GEC Trucking & Construction, Inc. be awarded the North Area.

Please feel free to contact me with any questions.

Sincerely,
EISMAN & RUSSO

John Pappas, P.E.
Program Manager

JP/jld

Eisman & Russo
CONSULTING ENGINEERS

ONE CITY ONE JACKSONVILLE

Countywide Program Management Services for Resurfacing & New Sidewalk Construction

May 1, 2024

Ms. Amy Griffin
City of Jacksonville
Right of Way / Stormwater Maintenance
609 St. Johns Bluff Road North
Jacksonville, FL 32225

Re: Pedestrian Safety Improvement Program – North, West and Southeast Areas;
Re- Bid No.: CP-0007-24
E&R City Contract # 71491-22; E&R Project # 2464-a; PO #: 650044-23

Dear Ms. Griffin:

EISMAN & RUSSO (E&R) has reviewed the three (3) re-bids submitted for the Pedestrian Safety Improvement Program – North, West and Southeast Areas; Bid No.: CP-0035-24

After review, E&R recognized that the Apparent Low Bidder (GEC Trucking & Construction, Inc.) submitted a bid that was significantly lower than the other two Bidders. Therefore, in an effort to confirm that there was no error by the Apparent Low Bidder, Eisman & Russo contacted the owner (Gene Carter, Sr.). Mr. Carter Sr. stated that he was comfortable with both the project scope and bid values that were included in the GEC Trucking & Construction, Inc. bid proposal. Consequently, E&R recommends GEC Trucking & Construction, Inc. be awarded the West Area.

Please feel free to contact me with any questions.

Sincerely,
EISMAN & RUSSO

John Pappas, P.E.
Program Manager

JP/jld

Eisman & Russo
CONSULTING ENGINEERS

ONE CITY ONE JACKSONVILLE

Countywide Program Management Services for Resurfacing & New Sidewalk Construction

May 1, 2024

Ms. Amy Griffin
City of Jacksonville
Right of Way / Stormwater Maintenance
609 St. Johns Bluff Road North
Jacksonville, FL 32225

Re: Pedestrian Safety Improvement Program – North, West and Southeast Areas;
Re- Bid No.: CP-0007-24
E&R City Contract # 71491-22; E&R Project # 2464-a; PO #: 650044-23

Dear Ms. Griffin:

EISMAN & RUSSO (E&R) has reviewed the three (3) re-bids submitted for the Pedestrian Safety Improvement Program – North, West and Southeast Areas; Bid No.: CP-0035-24

After review, E&R recognized that the Apparent Low Bidder (GEC Trucking & Construction, Inc.) submitted a bid that was significantly lower than the other two Bidders. Therefore, in an effort to confirm that there was no error by the Apparent Low Bidder, Eisman & Russo contacted the owner (Gene Carter, Sr.). Mr. Carter Sr. stated that he was comfortable with both the project scope and bid values that were included in the GEC Trucking & Construction, Inc. bid proposal. Consequently, E&R recommends GEC Trucking & Construction, Inc. be awarded the Southeast Area.

Please feel free to contact me with any questions.

Sincerely,
EISMAN & RUSSO

John Pappas, P.E.
Program Manager

JP/jld

Eisman & Russo
CONSULTING ENGINEERS

Department of Finance and Administration

A NEW DAY.

May 3, 2024

To: Dustin L. Freeman, Chief
Procurement Division

From: Gregory Grant, EBO/JSEB Administrator GG
LaRoy Covington, Business Compliance Analyst LC
Equal Business Opportunity Office / Jacksonville Small & Emerging Business Program

Re: CP-0035-24 Pedestrian Safety Improvement Program - North, West, and Southeast Areas - Re-Bid

The Equal Business Opportunity Office has reviewed the lowest bidder/ proposer for compliance with the Jacksonville Small and Emerging Business (JSEB) program. Based upon the review, and the areas of certification, the lowest bidder/proposer is **GEC Trucking & Construction, Inc.** with a total bid of **$548,880.00.** Based upon review of the JSEB schedule of work, the letters of intent, and the areas of certification, the lowest bidders/proposers meet the goal by utilizing **20%** JSEB participation with the following JSEB:

JSEB	Amount
GEC Trucking & Construction, Inc.	$548,880.00

Our review efforts are documented and available upon request. Please let us know if you have any questions or concerns. I can be reached at (904) 255-8833.

cc: Dave Klages
Gregory Grant

BID TABULATION
SUMMARY

		C.A.P. Contracting, Inc.	GEC Trucking & Construction, Inc.	Jax Utilities Management, Inc.	ONAS Corporation
Title:	Pedestrian Safety Improvement Program - North, West, and Southeast Areas - Re-Bid				
Bid No.:	CP-0035-24				
Close Date:	April 17, 2024				
Analyst:	David Klages				
No. Invited:	(10) **No. Received:** (4) **Other:** (0)				
Announcer:	Michelle Spitler				
Recorded By:	Melissa Pierce				
North Area Total Bid (Items 1 - 127):		**$1,080,100.00**	**$548,880.00**	**$1,162,346.00**	**$642,170.00**
West Area Total Bid (Items 1 - 127):		**$1,080,100.00**	**$548,880.00**	**$1,162,346.00**	**$642,170.00**
Southeast Area Total Bid (Items 1 - 127):		**$1,080,100.00**	**$548,880.00**	**$1,162,346.00**	**$642,170.00**
Bid Form:		Yes	Yes	Yes	Yes
Bid Proposal Form:		Yes	Yes	Yes	Yes
Conflict of Interest Certificate:		Yes	Yes	Yes	Yes
Acknowledgement/Commitment Form - Ex-Offenders:		Yes	Yes	Yes	Yes
JSEB Forms:		Yes	JSEB - Not Required	Yes	Yes
Meets JSEB Requirements:		Yes	Yes	Yes	Yes
Bid Bond:		Yes	Yes	Yes	Yes
Pre-Approval - Horizontal:		Yes	Yes	Yes	Yes
Addenda:		N/A	N/A	N/A	N/A

BID TABULATION
***Pricing is the same for all areas.**

Title:	Pedestrian Safety Improvement Program - North, West, and Southeast Areas - Re-Bid
Bid No.:	CP-0035-24
Close Date:	April 17, 2024
Analyst:	David Klages
No. Invited:	(10) No. Received: (4) Other: (0)
Announcer:	Michelle Spitler
Recorded By:	Melissa Pierce

Item #	Description	Unit of Measure	Est. Qty.	C.A.P. Contracting, Inc. Unit Price	C.A.P. Contracting, Inc. Extended Price	GEC Trucking & Construction, Inc. Unit Price	GEC Trucking & Construction, Inc. Extended Price	Jax Utilities Management, Inc. Unit Price	Jax Utilities Management, Inc. Extended Price	ONAS Corporation Unit Price	ONAS Corporation Extended Price
1	4" CONCRETE SIDEWALK	SY	3,000	$ 74.00	$222,000.00	$ 59.81	$179,430.00	$ 69.00	$207,000.00	$ 70.00	$210,000.00
2	5" CONCRETE SIDEWALK	SY	300	$ 78.00	$ 23,400.00	$ 62.44	$ 18,732.00	$ 77.00	$ 23,100.00	$ 71.00	$ 21,300.00
3	6" CONCRETE SIDEWALK	SY	100	$ 85.00	$ 8,500.00	$ 64.88	$ 6,488.00	$ 84.00	$ 8,400.00	$ 72.00	$ 7,200.00
4	5' WIDE SIMULATED TILE WALK (4" THICK)	SY	100	$ 78.00	$ 7,800.00	$ 40.00	$ 4,000.00	$ 76.00	$ 7,600.00	$ 75.00	$ 7,500.00
5	5' WIDE SIMULATED TILE WALK (5" THICK)	SY	100	$ 82.00	$ 8,200.00	$ 44.00	$ 4,400.00	$ 80.00	$ 8,000.00	$ 76.00	$ 7,600.00
6	5' WIDE SIMULATED TILE WALK (6" THICK)	SY	100	$ 87.00	$ 8,700.00	$ 45.00	$ 4,500.00	$ 84.00	$ 8,400.00	$ 78.00	$ 7,800.00
7	TREE REMOVAL (6" TO 12" DBH)	EA	10	$ 500.00	$ 5,000.00	$ 275.00	$ 2,750.00	$ 500.00	$ 5,000.00	$ 100.00	$ 1,000.00
8	TREE REMOVAL (> 12" TO 18" DBH)	EA	5	$ 750.00	$ 3,750.00	$ 240.00	$ 1,200.00	$ 1,490.00	$ 7,450.00	$ 130.00	$ 650.00
9	TREE REMOVAL (> 18" TO 24" DBH)	EA	5	$ 950.00	$ 4,750.00	$ 200.00	$ 1,000.00	$ 1,840.00	$ 9,200.00	$ 200.00	$ 1,000.00
10	TREE REMOVAL (> 24" TO 36" DBH)	EA	3	$ 1,250.00	$ 3,750.00	$ 250.00	$ 750.00	$ 2,900.00	$ 8,700.00	$ 250.00	$ 750.00
11	TREE REMOVAL (>36" TO 48" DBH)	EA	2	$ 2,200.00	$ 4,400.00	$ 200.00	$ 400.00	$ 3,900.00	$ 7,800.00	$ 400.00	$ 800.00
12	TREE REMOVAL (>48" DBH)	EA	2	$ 3,000.00	$ 6,000.00	$ 270.00	$ 540.00	$ 5,700.00	$ 11,400.00	$ 500.00	$ 1,000.00
13	EXISTING STUMP REMOVAL (6" TO 12" DIA.)	EA	6	$ 250.00	$ 1,500.00	$ 175.00	$ 1,050.00	$ 400.00	$ 2,400.00	$ 45.00	$ 270.00
14	EXISTING STUMP REMOVAL (>12" TO 24" DIA.)	EA	6	$ 300.00	$ 1,800.00	$ 175.00	$ 1,050.00	$ 1,100.00	$ 6,600.00	$ 55.00	$ 330.00
15	EXISTING STUMP REMOVAL (>24" TO 36" DIA.)	EA	3	$ 325.00	$ 975.00	$ 65.00	$ 195.00	$ 1,900.00	$ 5,700.00	$ 65.00	$ 195.00
16	EXISTING STUMP REMOVAL (>36" DIA.)	EA	2	$ 350.00	$ 700.00	$ 100.00	$ 200.00	$ 2,500.00	$ 5,000.00	$ 100.00	$ 200.00
17	PIPE REMOVAL (15" or less)	LF	50	$ 15.00	$ 750.00	$ 7.00	$ 350.00	$ 24.00	$ 1,200.00	$ 15.00	$ 750.00
18	PIPE REMOVAL (18" AND 24")	LF	50	$ 30.00	$ 1,500.00	$ 11.00	$ 550.00	$ 29.00	$ 1,450.00	$ 16.00	$ 800.00
19	PIPE REMOVAL (30" AND 36")	LF	50	$ 30.00	$ 1,500.00	$ 12.00	$ 600.00	$ 36.00	$ 1,800.00	$ 18.00	$ 900.00
20	PIPE REMOVAL (42" AND 48")	LF	50	$ 50.00	$ 2,500.00	$ 40.00	$ 2,000.00	$ 39.00	$ 1,950.00	$ 40.00	$ 2,000.00
21	PIPE REMOVAL (54" AND LARGER)	LF	30	$ 75.00	$ 2,250.00	$ 50.00	$ 1,500.00	$ 40.00	$ 1,200.00	$ 50.00	$ 1,500.00
22	HEADWALL REMOVAL	EA	6	$ 1,250.00	$ 7,500.00	$ 120.00	$ 720.00	$ 350.00	$ 2,100.00	$ 200.00	$ 1,200.00
23	INLET STRUCTURE REMOVAL	EA	6	$ 1,250.00	$ 7,500.00	$ 100.00	$ 600.00	$ 250.00	$ 1,500.00	$ 200.00	$ 1,200.00
24	CLEARING AND GRUBBING	SY	600	$ 15.00	$ 9,000.00	$ 12.00	$ 7,200.00	$ 11.00	$ 6,600.00	$ 8.00	$ 4,800.00
25	CONCRETE COPING WALL, 6" THICK (OVER 0' TO 1', HIGH)	LF	100	$ 45.00	$ 4,500.00	$ 11.00	$ 1,100.00	$ 24.00	$ 2,400.00	$ 25.00	$ 2,500.00
26	CONCRETE COPING WALL, 6" THICK (OVER 1' TO 2', HIGH)	LF	100	$ 50.00	$ 5,000.00	$ 11.00	$ 1,100.00	$ 35.00	$ 3,500.00	$ 28.00	$ 2,800.00
27	CONCRETE TURN-DOWN, 4" THICK (0" TO 12" DEEP)	LF	150	$ 40.00	$ 6,000.00	$ 13.00	$ 1,950.00	$ 25.00	$ 3,750.00	$ 12.00	$ 1,800.00
28	CONCRETE TURN-DOWN, 4" THICK (OVER 12" TO 18" DEEP)	LF	50	$ 50.00	$ 2,500.00	$ 14.00	$ 700.00	$ 24.00	$ 1,200.00	$ 14.00	$ 700.00
29	PIPE, PVC, SCH. 40, 6" DRAIN	LF	30	$ 25.00	$ 750.00	$ 8.00	$ 240.00	$ 20.00	$ 600.00	$ 8.00	$ 240.00
30	ROADWAY SHOULDER GRADING (0' TO 2' WIDE)	LF	100	$ 20.00	$ 2,000.00	$ 25.00	$ 2,500.00	$ 8.00	$ 800.00	$ 6.00	$ 600.00
31	ROADWAY SHOULDER GRADING (>2' TO 4' WIDE)	LF	75	$ 20.00	$ 1,500.00	$ 29.00	$ 2,175.00	$ 11.00	$ 825.00	$ 8.00	$ 600.00
32	ROADWAY SHOULDER GRADING (>4' TO 6' WIDE)	LF	60	$ 25.00	$ 1,500.00	$ 30.00	$ 1,800.00	$ 16.00	$ 960.00	$ 6.00	$ 360.00

BID TABULATION
***Pricing is the same for all areas.**

Title:	Pedestrian Safety Improvement Program - North, West, and Southeast Areas - Re-Bid
Bid No.:	CP-0035-24
Close Date:	April 17, 2024
Analyst:	David Klages
No. Invited:	(10) No. Received: (4) Other: (0)
Announcer:	Michelle Spitler
Recorded By:	Melissa Pierce

				C.A.P. Contracting, Inc.		GEC Trucking & Construction, Inc.		Jax Utilities Management, Inc.		ONAS Corporation	
Item #	**Description**	**Unit of Measure**	**Est. Qty.**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**
33	DITCH REGRADING (0' TO 2' DEEP)	LF	500	$ 20.00	$ 10,000.00	$ 2.00	$ 1,000.00	$ 11.00	$ 5,500.00	$ 5.00	$ 2,500.00
34	DITCH REGRADING (>2' TO 4' DEEP)	LF	300	$ 20.00	$ 6,000.00	$ 2.25	$ 675.00	$ 13.00	$ 3,900.00	$ 6.00	$ 1,800.00
35	DITCH REGRADING (>4' TO 6' DEEP)	LF	50	$ 25.00	$ 1,250.00	$ 2.50	$ 125.00	$ 12.00	$ 600.00	$ 7.00	$ 350.00
36	TILE SIDEWALK REMOVAL	SY	50	$ 20.00	$ 1,000.00	$ 2.00	$ 100.00	$ 17.00	$ 850.00	$ 5.00	$ 250.00
37	ASPHALT PAVEMENT REMOVAL	SY	50	$ 30.00	$ 1,500.00	$ 5.00	$ 250.00	$ 15.00	$ 750.00	$ 8.00	$ 400.00
38	CONCRETE REMOVAL (0" TO 6" THICK)	SY	200	$ 25.00	$ 5,000.00	$ 18.00	$ 3,600.00	$ 17.00	$ 3,400.00	$ 11.00	$ 2,200.00
39	CURB AND GUTTER REMOVAL	LF	50	$ 20.00	$ 1,000.00	$ 18.00	$ 900.00	$ 12.00	$ 600.00	$ 15.00	$ 750.00
40	CURB REMOVAL FOR HANDICAP RAMP CONSTRUCTION	LF	50	$ 25.00	$ 1,250.00	$ 20.00	$ 1,000.00	$ 13.00	$ 650.00	$ 20.00	$ 1,000.00
41	EXISTING SIDEWALK REMOVAL & HANDICAP RAMP INSTALLATION	SY	100	$ 250.00	$ 25,000.00	$ 120.00	$ 12,000.00	$ 140.00	$ 14,000.00	$ 200.00	$ 20,000.00
42	CITY STANDARD CURB AND GUTTER	LF	100	$ 40.00	$ 4,000.00	$ 52.00	$ 5,200.00	$ 54.00	$ 5,400.00	$ 28.00	$ 2,800.00
43	ASPHALT REPAIR, CITY STANDARD (TYPE S-1 OR TYPE III)	SY	50	$ 200.00	$ 10,000.00	$ 38.00	$ 1,900.00	$ 62.00	$ 3,100.00	$ 60.00	$ 3,000.00
44	STORM SEWER CURB INLET, 2' TO 6' DEPTH (D-201)	EA	3	$ 4,000.00	$ 12,000.00	$ 1,500.00	$ 4,500.00	$ 3,800.00	$ 11,400.00	$ 1,500.00	$ 4,500.00
45	STORM SEWER CURB INLET, 48" ID, >2' TO 6' DEPTH (D-203)	EA	3	$ 5,000.00	$ 15,000.00	$ 1,700.00	$ 5,100.00	$ 4,600.00	$ 13,800.00	$ 1,700.00	$ 5,100.00
46	CITY STD. TYPE "B" INLET, 3' X 3', >2' TO 6' DEPTH (D-205)	EA	3	$ 4,000.00	$ 12,000.00	$ 1,300.00	$ 3,900.00	$ 5,241.00	$ 15,723.00	$ 1,800.00	$ 5,400.00
47	CITY STD. TYPE "B" INLET, 4' X 4', > 2' TO 6' DEPTH (D-205)	EA	3	$ 4,000.00	$ 12,000.00	$ 1,300.00	$ 3,900.00	$ 5,700.00	$ 17,100.00	$ 1,900.00	$ 5,700.00
48	CITY STD. TYPE "C" INLET, >2' TO 6' DEPTH (D-207)	EA	3	$ 4,200.00	$ 12,600.00	$ 1,500.00	$ 4,500.00	$ 2,110.00	$ 6,330.00	$ 1,700.00	$ 5,100.00
49	CITY STD. TYPE "E" INLET, >2' TO 6' DEPTH (D-208)	EA	3	$ 4,000.00	$ 12,000.00	$ 1,600.00	$ 4,800.00	$ 2,900.00	$ 8,700.00	$ 1,800.00	$ 5,400.00
50	CITY STD. TYPE "J-1" MANHOLE/INLET, > 2' TO 6' DEPTH (D-101)	EA	4	$ 7,150.00	$ 28,600.00	$ 1,600.00	$ 6,400.00	$ 4,660.00	$ 18,640.00	$ 2,000.00	$ 8,000.00
51	CITY STD. TYPE "J-2" MANHOLE, 4' X 4', 2' TO 6' DEPTH (D-102)	EA	4	$ 7,000.00	$ 28,000.00	$ 1,650.00	$ 6,600.00	$ 5,640.00	$ 22,560.00	$ 2,500.00	$ 10,000.00
52	15" RCP, 0' TO 6' DEPTH	LF	50	$ 70.00	$ 3,500.00	$ 60.00	$ 3,000.00	$ 79.00	$ 3,950.00	$ 70.00	$ 3,500.00
53	12" X 18" ERCP, 0' TO 6' DEPTH	LF	50	$ 90.00	$ 4,500.00	$ 75.00	$ 3,750.00	$ 82.00	$ 4,100.00	$ 75.00	$ 3,750.00
54	18" RCP, 0' TO 6' DEPTH	LF	50	$ 95.00	$ 4,750.00	$ 50.00	$ 2,500.00	$ 83.00	$ 4,150.00	$ 80.00	$ 4,000.00
55	14" X 23" ERCP, 0' TO 6" DEPTH	LF	50	$ 105.00	$ 5,250.00	$ 75.00	$ 3,750.00	$ 85.00	$ 4,250.00	$ 85.00	$ 4,250.00
56	24" RCP, 0' TO 6' DEPTH	LF	50	$ 110.00	$ 5,500.00	$ 80.00	$ 4,000.00	$ 97.00	$ 4,850.00	$ 88.00	$ 4,400.00
57	19" X 30" ERCP, 0' TO 6' DEPTH	LF	25	$ 150.00	$ 3,750.00	$ 120.00	$ 3,000.00	$ 99.00	$ 2,475.00	$ 120.00	$ 3,000.00
58	30" RCP, 0' TO 6' DEPTH	LF	25	$ 155.00	$ 3,875.00	$ 125.00	$ 3,125.00	$ 91.00	$ 2,275.00	$ 130.00	$ 3,250.00
59	24" X 38" ERCP, 0' TO 6' DEPTH	LF	25	$ 210.00	$ 5,250.00	$ 160.00	$ 4,000.00	$ 115.00	$ 2,875.00	$ 140.00	$ 3,500.00
60	36" RCP, 0' TO 6' DEPTH	LF	25	$ 220.00	$ 5,500.00	$ 100.00	$ 2,500.00	$ 197.00	$ 4,925.00	$ 150.00	$ 3,750.00
61	29" X 45" ERCP, 0' TO 6' DEPTH	LF	25	$ 300.00	$ 7,500.00	$ 250.00	$ 6,250.00	$ 229.00	$ 5,725.00	$ 160.00	$ 4,000.00
62	15" CMP, 0' TO 6' DEPTH	LF	350	$ 60.00	$ 21,000.00	$ 40.00	$ 14,000.00	$ 61.00	$ 21,350.00	$ 60.00	$ 21,000.00
63	18" X 11" CMP, 0' TO 6' DEPTH	LF	250	$ 70.00	$ 17,500.00	$ 31.00	$ 7,750.00	$ 75.00	$ 18,750.00	$ 75.00	$ 18,750.00
64	18" CMP, 0' TO 6' DEPTH	LF	200	$ 75.00	$ 15,000.00	$ 48.00	$ 9,600.00	$ 72.00	$ 14,400.00	$ 85.00	$ 17,000.00

BID TABULATION
***Pricing is the same for all areas.**

Title:	Pedestrian Safety Improvement Program - North, West, and Southeast Areas - Re-Bid
Bid No.:	CP-0035-24
Close Date:	April 17, 2024
Analyst:	David Klages
No. Invited:	(10) No. Received: (4) Other: (0)
Announcer:	Michelle Spitler
Recorded By:	Melissa Pierce

Item #	Description	Unit of Measure	Est. Qty.	C.A.P. Contracting, Inc. Unit Price	C.A.P. Contracting, Inc. Extended Price	GEC Trucking & Construction, Inc. Unit Price	GEC Trucking & Construction, Inc. Extended Price	Jax Utilities Management, Inc. Unit Price	Jax Utilities Management, Inc. Extended Price	ONAS Corporation Unit Price	ONAS Corporation Extended Price
65	22" X 13" CMP, 0' TO 6' DEPTH	LF	200	$ 85.00	$ 17,000.00	$ 42.00	$ 8,400.00	$ 81.00	$ 16,200.00	$ 90.00	$ 18,000.00
66	24" CMP, 0' TO 6' DEPTH	LF	100	$ 100.00	$ 10,000.00	$ 75.00	$ 7,500.00	$ 76.00	$ 7,600.00	$ 50.00	$ 5,000.00
67	29" X 18" CMP, 0' TO 6' DEPTH	LF	100	$ 105.00	$ 10,500.00	$ 52.00	$ 5,200.00	$ 86.00	$ 8,600.00	$ 100.00	$ 10,000.00
68	30" CMP, 0' TO 6' DEPTH	LF	50	$ 130.00	$ 6,500.00	$ 115.00	$ 5,750.00	$ 88.00	$ 4,400.00	$ 110.00	$ 5,500.00
69	36" X 22" CMP, 0' TO 6' DEPTH	LF	50	$ 160.00	$ 8,000.00	$ 62.00	$ 3,100.00	$ 96.00	$ 4,800.00	$ 120.00	$ 6,000.00
70	42" X 29" CMP, 0' TO 6' DEPTH	LF	25	$ 175.00	$ 4,375.00	$ 90.00	$ 2,250.00	$ 120.00	$ 3,000.00	$ 130.00	$ 3,250.00
71	CAST IN-PLACE, REINFORCED CONCRETE FOR MISC., WALL, PARAPET	CY	20	$ 500.00	$ 10,000.00	$ 275.00	$ 5,500.00	$ 2,950.00	$ 59,000.00	$ 400.00	$ 8,000.00
72	PRECAST STRAIGHT ENDWALL FOR 15" OR 12" X 18" PIPE (D-408)	EA	2	$ 675.00	$ 1,350.00	$ 950.00	$ 1,900.00	$ 1,974.00	$ 3,948.00	$ 900.00	$ 1,800.00
73	PRECAST STRAIGHT ENDWALL FOR 18" OR 14" X 23" PIPE (D-408)	EA	2	$ 775.00	$ 1,550.00	$ 1,000.00	$ 2,000.00	$ 2,129.00	$ 4,258.00	$ 950.00	$ 1,900.00
74	PRECAST STRAIGHT ENDWALL FOR 24" OR 19" X 30" PIPE (D-408)	EA	2	$ 1,550.00	$ 3,100.00	$ 1,000.00	$ 2,000.00	$ 2,940.00	$ 5,880.00	$ 1,100.00	$ 2,200.00
75	PRECAST STRAIGHT ENDWALL FOR 30" OR 24" X 38" PIPE (D-408)	EA	2	$ 2,500.00	$ 5,000.00	$ 1,999.00	$ 3,998.00	$ 4,409.00	$ 8,818.00	$ 2,600.00	$ 5,200.00
76	PRECAST STRAIGHT ENDWALL FOR 36" OR 29" X 45" PIPE (D-408)	EA	2	$ 3,000.00	$ 6,000.00	$ 2,395.00	$ 4,790.00	$ 5,854.00	$ 11,708.00	$ 2,800.00	$ 5,600.00
77	MITR'D. END- SECTION FOR 15" RCP OR CMP D/W CULVERTS (D-429)	EA	5	$ 1,000.00	$ 5,000.00	$ 750.00	$ 3,750.00	$ 949.00	$ 4,745.00	$ 500.00	$ 2,500.00
78	MITR'D. END- SECTION FOR 18" RCP OR CMP D/W CULVERTS (D-429)	EA	5	$ 1,300.00	$ 6,500.00	$ 800.00	$ 4,000.00	$ 1,092.00	$ 5,460.00	$ 600.00	$ 3,000.00
79	MITR'D END- SECTION FOR 12 X 18" E RCP OR 13" X 17" CMPA (D-430)	EA	5	$ 1,400.00	$ 7,000.00	$ 500.00	$ 2,500.00	$ 1,200.00	$ 6,000.00	$ 700.00	$ 3,500.00
80	MITR'D. END- SECTION FOR 14" X23" E RCP OR 15" X 21" CMPA (D-430)	EA	5	$ 1,650.00	$ 8,250.00	$ 500.00	$ 2,500.00	$ 1,800.00	$ 9,000.00	$ 800.00	$ 4,000.00
81	MITR'D. END-SECTION FOR 19" X 30" ERCP OR 20" X 28" CMPA (D-430)	EA	2	$ 2,200.00	$ 4,400.00	$ 500.00	$ 1,000.00	$ 2,600.00	$ 5,200.00	$ 900.00	$ 1,800.00
82	STD. MITR'D. END-SECTION FOR 24" RCP OR CMP (D-431)	EA	3	$ 2,300.00	$ 6,900.00	$ 500.00	$ 1,500.00	$ 1,439.00	$ 4,317.00	$ 900.00	$ 2,700.00
83	STD. MITR'D. END-SECTION FOR 30" RCP OR CMP (D-431)	EA	3	$ 2,500.00	$ 7,500.00	$ 500.00	$ 1,500.00	$ 1,910.00	$ 5,730.00	$ 950.00	$ 2,850.00
84	EROSION CONTROL, HAY BALES	EA	100	$ 20.00	$ 2,000.00	$ 1.00	$ 100.00	$ 10.00	$ 1,000.00	$ 5.00	$ 500.00
85	EROSION CONTROL, SILT BARRIER/FABRIC	LF	100	$ 10.00	$ 1,000.00	$ 1.50	$ 150.00	$ 4.00	$ 400.00	$ 3.00	$ 300.00
86	GRASSING, SOD	SY	800	$ 20.00	$ 16,000.00	$ 20.00	$ 16,000.00	$ 11.29	$ 9,032.00	$ 10.00	$ 8,000.00
87	GRASSING, SEED AND MULCH	SY	3,000	$ 3.00	$ 9,000.00	$ 1.62	$ 4,860.00	$ 4.00	$ 12,000.00	$ 1.50	$ 4,500.00
88	FILL, "A-3" SAND OR BETTER	CY	250	$ 25.00	$ 6,250.00	$ 21.50	$ 5,375.00	$ 29.00	$ 7,250.00	$ 15.00	$ 3,750.00
89	FENCE RELOCATION	LF	100	$ 25.00	$ 2,500.00	$ 1.00	$ 100.00	$ 37.00	$ 3,700.00	$ 6.00	$ 600.00
90	NEW 4' CHAIN LINK FENCE	LF	75	$ 50.00	$ 3,750.00	$ 10.00	$ 750.00	$ 31.00	$ 2,325.00	$ 12.00	$ 900.00
91	NEW 6' CHAIN LINK FENCE	LF	75	$ 75.00	$ 5,625.00	$ 10.00	$ 750.00	$ 48.00	$ 3,600.00	$ 15.00	$ 1,125.00
92	BUSH RELOCATION	EA	20	$ 50.00	$ 1,000.00	$ 1.00	$ 20.00	$ 75.00	$ 1,500.00	$ 8.00	$ 160.00
93	PALM TREE RELOCATION	EA	5	$ 1,500.00	$ 7,500.00	$ 50.00	$ 250.00	$ 190.00	$ 950.00	$ 100.00	$ 500.00
94	SIGN RELOCATION (PER POST)	EA	10	$ 50.00	$ 500.00	$ 5.00	$ 50.00	$ 110.00	$ 1,100.00	$ 8.00	$ 80.00
95	MAILBOX RELOCATION (USING EXIST. POST)	EA	10	$ 100.00	$ 1,000.00	$ 5.00	$ 50.00	$ 70.00	$ 700.00	$ 8.00	$ 80.00
96	MANHOLE ADJUSTMENT (OVER 10" DIA.)	EA	4	$ 450.00	$ 1,800.00	$ 25.00	$ 100.00	$ 390.00	$ 1,560.00	$ 150.00	$ 600.00

BID TABULATION
***Pricing is the same for all areas.**

Title:	Pedestrian Safety Improvement Program - North, West, and Southeast Areas - Re-Bid
Bid No.:	CP-0035-24
Close Date:	April 17, 2024
Analyst:	David Klages
No. Invited:	(10) No. Received: (4) Other: (0)
Announcer:	Michelle Spitler
Recorded By:	Melissa Pierce

				C.A.P. Contracting, Inc.		GEC Trucking & Construction, Inc.		Jax Utilities Management, Inc.		ONAS Corporation	
Item #	**Description**	**Unit of Measure**	**Est. Qty.**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**	**Unit Price**	**Extended Price**
97	METER BOX ADJUSTMENT	EA	5	$ 250.00	$ 1,250.00	$ 5.00	$ 25.00	$ 290.00	$ 1,450.00	$ 20.00	$ 100.00
98	VALVE BOX ADJUSTMENT	EA	5	$ 300.00	$ 1,500.00	$ 5.00	$ 25.00	$ 170.00	$ 850.00	$ 20.00	$ 100.00
99	INLET TOP ADJUSTMENT, UP TO 1 FOOT	EA	2	$ 450.00	$ 900.00	$ 35.00	$ 70.00	$ 650.00	$ 1,300.00	$ 90.00	$ 180.00
100	INLET TOP ADJUSTMENT, FROM 1 FOOT TO 2 FEET	EA	2	$ 500.00	$ 1,000.00	$ 65.00	$ 130.00	$ 829.00	$ 1,658.00	$ 120.00	$ 240.00
101	MANHOLE FRAME AND COVER, CITY STANDARD	EA	5	$ 550.00	$ 2,750.00	$ 100.00	$ 500.00	$ 580.00	$ 2,900.00	$ 200.00	$ 1,000.00
102	INLET FRAME AND GRATE, CITY STANDARD	EA	5	$ 600.00	$ 3,000.00	$ 150.00	$ 750.00	$ 992.00	$ 4,960.00	$ 350.00	$ 1,750.00
103	CONCRETE TRENCH DRAIN (4' to 6' SIDEWALK)	EA	3	$ 3,000.00	$ 9,000.00	$ 400.00	$ 1,200.00	$ 890.00	$ 2,670.00	$ 400.00	$ 1,200.00
104	3.5' H STEEL PIPE GUIDERAIL	LF	50	$ 350.00	$ 17,500.00	$ 300.00	$ 15,000.00	$ 110.00	$ 5,500.00	$ 120.00	$ 6,000.00
104A	3.5' H ALUMINUM PIPE GUIDERAIL	LF	50	$ 350.00	$ 17,500.00	$ 300.00	$ 15,000.00	$ 175.00	$ 8,750.00	$ 120.00	$ 6,000.00
105	SAW CUT EXISTING CONCRETE STRUCTURE FOR 18" or less PIPE "TIE-IN"	EA	2	$ 1,000.00	$ 2,000.00	$ 60.00	$ 120.00	$ 1,210.00	$ 2,420.00	$ 60.00	$ 120.00
106	SAW CUT EXISTING CONCRETE STRUCTURE FOR 24" to 30" PIPE "TIE-IN"	EA	2	$ 1,250.00	$ 2,500.00	$ 65.00	$ 130.00	$ 1,900.00	$ 3,800.00	$ 65.00	$ 130.00
107	SAW CUT EXISTING CONCRETE STRUCTURE FOR 36" to 42" PIPE "TIE-IN"	EA	2	$ 1,500.00	$ 3,000.00	$ 65.00	$ 130.00	$ 2,800.00	$ 5,600.00	$ 70.00	$ 140.00
108	IRRIGATION PIPE, 1/2" to 1" SCHEDULE 40 PVC	LF	50	$ 25.00	$ 1,250.00	$ 2.00	$ 100.00	$ 15.00	$ 750.00	$ 10.00	$ 500.00
109	SPRINKLER HEAD RELOCATION	EA	10	$ 30.00	$ 300.00	$ 10.00	$ 100.00	$ 150.00	$ 1,500.00	$ 12.00	$ 120.00
110	TRENCH PROTECTION	LF	50	$ 75.00	$ 3,750.00	$ 5.00	$ 250.00	$ 80.00	$ 4,000.00	$ 10.00	$ 500.00
111	PROJECT SIGNS	EA	10	$ 400.00	$ 4,000.00	$ 5.00	$ 50.00	$ 560.00	$ 5,600.00	$ 20.00	$ 200.00
112	DETECTABLE WARNINGS ON WALKING SURFACES	SF	200	$ 35.00	$ 7,000.00	$ 25.00	$ 5,000.00	$ 30.00	$ 6,000.00	$ 30.00	$ 6,000.00
113	6" LIMEROCK + STABILIZING	SY	50	$ 80.00	$ 4,000.00	$ 15.00	$ 750.00	$ 39.00	$ 1,950.00	$ 20.00	$ 1,000.00
114	4" CONCRETE DITCH PAVEMENT	SY	50	$ 75.00	$ 3,750.00	$ 60.00	$ 3,000.00	$ 75.00	$ 3,750.00	$ 95.00	$ 4,750.00
115	LIMEROCK COMPACTED IN PLACE	CY	10	$ 45.00	$ 450.00	$ 25.00	$ 250.00	$ 150.00	$ 1,500.00	$ 30.00	$ 300.00
116	ASPHALT TYPE S-1	TON	20	$ 350.00	$ 7,000.00	$ 150.00	$ 3,000.00	$ 360.00	$ 7,200.00	$ 120.00	$ 2,400.00
117	ASPHALT TYPE S-3	TON	20	$ 375.00	$ 7,500.00	$ 140.00	$ 2,800.00	$ 380.00	$ 7,600.00	$ 130.00	$ 2,600.00
118	VARIABLE MESSAGE BOARD (PER DAY)	EA	4	$ 75.00	$ 300.00	$ 54.00	$ 216.00	$ 95.00	$ 380.00	$ 50.00	$ 200.00
119	POLICEMAN HOURS (per each including administrative fees)	HR	40	$ 100.00	$ 4,000.00	$ 32.40	$ 1,296.00	$ 75.00	$ 3,000.00	$ 30.00	$ 1,200.00
120	MAINTENANCE OF TRAFFIC P.O. UP TO $10,000 IN VALUE	LS	5	$ 1,500.00	$ 7,500.00	$ 625.00	$ 3,125.00	$ 3,200.00	$ 16,000.00	$ 600.00	$ 3,000.00
121	MAINTENANCE OF TRAFFIC P.O. VALUE FROM $10,001 TO $20,000	LS	5	$ 2,000.00	$ 10,000.00	$ 625.00	$ 3,125.00	$ 3,440.00	$ 17,200.00	$ 700.00	$ 3,500.00
122	MAINTENANCE OF TRAFFIC P.O. VALUE FROM $20,001 TO $30,000	LS	4	$ 2,500.00	$ 10,000.00	$ 600.00	$ 2,400.00	$ 4,330.00	$ 17,320.00	$ 800.00	$ 3,200.00
123	MAINTENANCE OF TRAFFIC P.O. VALUE FROM $30,001 TO $50,000	LS	3	$ 3,500.00	$ 10,500.00	$ 600.00	$ 1,800.00	$ 5,833.00	$ 17,499.00	$ 900.00	$ 2,700.00
124	MAINTENANCE OF TRAFFIC P.O. VALUE FROM $50,001 TO $75,000	LS	3	$ 5,500.00	$ 16,500.00	$ 600.00	$ 1,800.00	$ 12,117.00	$ 36,351.00	$ 1,000.00	$ 3,000.00
125	MAINTENANCE OF TRAFFIC P.O. VALUE FROM $75,001 TO $100,000	LS	2	$ 7,500.00	$ 15,000.00	$ 600.00	$ 1,200.00	$ 17,680.00	$ 35,360.00	$ 1,100.00	$ 2,200.00
126	MAINTENANCE OF TRAFFIC P.O. VALUE FROM $100,001 TO $125,000	LS	2	$ 10,000.00	$ 20,000.00	$ 600.00	$ 1,200.00	$ 22,198.00	$ 44,396.00	$ 1,200.00	$ 2,400.00
127	MAINTENANCE OF TRAFFIC P.O. VALUE FROM $125,001 TO $150,000	LS	2	$ 15,000.00	$ 30,000.00	$ 600.00	$ 1,200.00	$ 29,344.00	$ 58,688.00	$ 1,400.00	$ 2,800.00

B. BASIS OF AWARD

The project may be awarded **By Area** to the lowest responsive, responsible Bidder for the Total Base Bid contingent on the availability of funds within the project's approved budget. The City has the right to reject any or all bids if it is in the best interest of the City.

C. REVISIONS OF BID PROPOSAL FORM

Request for revision of the Bid Proposal Form must be made to the ENGINEER at least ten (10) days prior to date of opening of Bids. Revision of the Bid Proposal by the Bidder will void the Bid.

D. CONTRACT EXPIRATION DATE

The Contract expiration date shall be established 120 calendar days after the scheduled construction completion date in order to comply with Executive Order 2013-05.

E. BID CHANGES

No changes in the amount of Bids appearing on the outside of Bids will be considered. Only the amounts shown on bidding documents inside the envelope will be considered. All changes, corrections and erasures must be initialed by the person signing the bid.

F. CONSTRUCTION COMPLETION

The intent of this contract is that the Contractor provides **Pedestrian Safety Improvement Program - North, West, and Southeast Areas (Re-Bid)** during the period of Fiscal Year 2024 (date of executed contract through September 30, 2024). The Contractor shall begin work within ten (10) calendar days, including Sundays and holidays, after issuance of a Blanket Order or Purchase Order from the City. No Blanket Orders or Purchase Orders will be issued under this Contract after September 30, 2024 unless the Contract is renewed. The active Contract will expire 120 days thereafter. All work started under a Blanket Order or Purchase Order shall be completed by the expiration date. By mutual agreement of both parties, provided funds are available, the Contract may be extended two (2) times for a period of one (1) year each. Each extension amendment of the contract will be amended prior to September 30th of the current contract fiscal year.

Based upon the agreement of all parties, the Contract Unit Prices may be adjusted one (1) time per fiscal year, after the initial contract term, based on the stated Consumer Price Index (CPI) for All Urban Consumers - South Region All Items, (Series CUURO300SAO), over the preceding twelve (12) months from the latter of the date of Contract Award or the date of the previously approved Contract Unit Price rate adjustments. The adjusted Contract Unit Prices will be calculated using the current Contract Unit Prices and adjusting them by the amount of the stated CPI.

PEDESTRIAN SAFETY IMPROVEMENT PROGRAM
NORTH, WEST AND SOUTHEAST AREAS

DUVAL COUNTY
2023 - 2024

SECTION 30

SCOPE OF WORK

30.1 SCOPE: The work covered by these plans and specifications consists of furnishing all labor, materials and equipment; and performing all operations necessary for the construction of concrete sidewalks and appurtenant work including enclosing existing drainage ditches as required for the installation of sidewalk at designated locations, as specified in the Contract Documents.

30.2 LOCATION: The work sites will be on any street, highway, or other City property located within the North, West and Southeast Areas within Duval County (See maps). However, at any time during the extent of this contract, the City may issue purchase orders to construct sidewalks in other areas of the City.

30.3 INTENT: It is the intent of this Contract to provide, upon request, well-constructed City standard sidewalks at various locations within the limits of the City of Jacksonville. It is not the intent of these Contract Documents to minutely define the mode, means, methods, techniques, sequence, or procedures of construction selected by the Contractor, or the safety precautions and programs incidental to the work of the Contractor, but rather to set forth reasonable and rational criteria for the construction thereof.