SUBJECT: **DEMO & SITE CLEARANCE OF FORTY (40) PROPERTIES**

BID# CF-0082-15 OPEN DATE: **2015-02-25**

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT:
CONSTRUCTION FIXED

AGENCY: **MUNICIPAL CODE**

BASIS OF AWARD: **BY ITEM TO THE LOWEST RESPONSIVE, RESPONSIBLE BIDDER**

NUMBER OF BIDS INVITED 7 NUMBER RECEIVED 5 OTHER 0

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:

Item #20 was awarded to Michael Lloyd Hauling on 03/26/15 in the amount of $4,400.00 which included $225.00 cost of asbestos survey as required by bid specifications. The performed asbestos survey requires both an asbestos abatement and wet demolition be performed prior to demolition. In accordance with the specifications, the awarded contractor solicited three quotes for the asbestos abatement from the following companies:
1) Bradco Environmental- $2,200.00; 2) Darcco Environmental- $2,400.00 and 3) Alachua Environmental Srvs- $3,000.00

Recommend approval to increase award for Item #20 to Michael Lloyd Hauling, in the amount of $2,200.00 for the asbestos abatement and $1,250.00 for wet demolition (total for both $3,450.00). Total revised award amount for Item #20 not-to-exceed $7,850.00.

This award to be funded by account: ERCD1N1FR-03410 to be executed by Purchase Order/Change Order.

Attachments: Recommendation Memo, Change Order, Vendor Quotes, Asbestos Report, Previous Award

BUYER: Marilyn Laidler
MARILYN LAIDLER

RESPECTFULLY SUBMITTED: _____
GREGORY PEASE, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: **Bryan Mosier, Chief, Municipal Code Compliance Division**

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE
MEMBERS APPROVING _____ MEMBERS DISAPPROVING _____ DATE: _____

_____ _____ OTHER: _____

_____ _____

_____ _____

ACTION OF AWARDING AUTHORITY DATE: _____

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

FORM GB-108, Revised 12/2007

NEIGHBORHOODS DEPARTMENT

MUNICIPAL CODE COMPLIANCE DIVISION

Jacksonville
Where Florida Begins.

March 21, 2017

M E M O R A N D U M

TO: Gregory Pease, Division Chief
Procurement Division

FROM: Bryan Mosier, Division Chief
Municipal Code Compliance Division

RE: Change Order Request for Item #20 on Formal Demolition Bid #CF-0082-15

The survey of condemned structure 3553 Mecca St revealed asbestos in the transite siding which a licensed asbestos abatement contractor must remove prior to demolition of this condemned structure. Asbestos was also found in the drywall system, texture paint, and chimney mastic which must be removed utilizing wet demolition method.

I recommend approval of the change order request submitted by Michael Lloyd Hauling in the amount of $3,450.00 (reference purchase order #7A03096).

Contractor	Item Number	Amount
Michael Lloyd Hauling	20	$3,450.00

Funding Source: ERCD1N1FR /03410

BM/mc

Michael Lloyd Hauling, Inc.

1601 Rudd Road
Jacksonville, FL 32220
PH 904-759-1861
FX 904-781-7670
Michaellloydhauling@outlook.com

Date 3/7/17

Mike,
I need to get a C/O for the following:

Address: 3553 Mecca Street
PO# 7A03096
Original Amount: $4400.00
For abatement
Change Order Amount: $2,200.00

Thank you,
Melissa Lloyd
Michael Lloyd Hauling Inc.

BRADCO ENVIRONMENTAL

5810 Stuart Avenue, Jacksonville FL 32254 904 334-3517

March 6, 2017

PROPOSAL

To: Michael Lloyd Hauling
1601 Rudd Road
Jacksonville, FL 32220
Attn: Michael Lloyd

RE: 3553 Mecca Street

Bradco Environmental proposes to furnish all labor, material, trucking, disposal and applicable notifications for the project listed above. This Material is friable and must be removed by a licensed Asbestos Contractor. Removal is performed by a licensed Asbestos Contractor in accordance with EPA and OSHA regulations.

- Remove ACM siding
- Provide air clearance from third-party lab

- Price includes trucking and disposal by EPA approved landfill facility.

Total Price $2,200.

Jerry F Bradley, President

PAYMENT FOR WORK PERFORMED UPON RECEIPT OF INVOICE.

ACCEPTANCE OF PROPOSAL

AUTHORIZED PARTY:_____ **DATE:** _____

THANK YOU FOR THE OPPORTUNITY TO DO BUSINESS

DARCCO
ENVIRONMENTAL, INC.

ATTN: Mr. Michael Lloyd

PROPOSAL / CONTRACT

Michael Lloyd Hauling, Inc. 1601 Rudd Road Jacksonville, Florida 32220 Phone: (904)759-4684 / Fax: 781-7670 eMail: michaellloydhauling@outlook.com	Date: 27-Feb-17	Proposal No: **17145-AB**
	Job Name: **Residential**	
	Job Location: **3553 Mecca Street** **Jacksonville, FL 32209**	

Darcco Environmental, Inc. is pleased to submit our proposal for the above mention job:

We propose to furnish all equipment, labor and materials to complete the following:

To remove and dispose of approximately 1,400 SF of asbestos containing transite siding from the exterior of the home.

Air Monitoring based upon personnel air monitoring only.
All asbestos abatement shall be performed in accordance with EPA and OSHA regulations.
All disposals shall be at an EPA approved and permitted landfill facility.
Please note we are not responsible for any paint that may be removed by tape.
We appreciate this opportunity to quote your special construction needs.

All the above work will be completed for the sum of: **$2,400.00**

TWO THOUSAND, FOUR HUNDRED DOLLARS AND ZERO CENTS

Payment to be made as follows: Payable in full upon completion.

Jerry W. Carter

Signature: _____ (ch) **Title:** President

Print Name: Jerry W. Carter **Date:** February 27, 2017

ACCEPTANCE OF PROPOSAL

Signature: _____ **Title:** _____

Print Name: _____ **Date:** _____

PLEASE SIGN AND RETURN ONE COPY UPON EXECUTION. THIS AGREEMENT BECOMES A LEGAL AND BINDING CONTRACT. IF AN ACTION BECOMES NECESSARY TO ENFORCE THIS CONTRACT, THE OWNER WILL BE RESPONSIBLE FOR THE ATTORNEY'S FEES AND THE COURT COSTS OF THE CONTRACTOR.

ALACHUA ENVIRONMENTAL SERVICES, INC.
Post Office Box 1208 | Glen St. Mary, Florida 32040 | Phone: 904-259-6200
Asbestos License #ZA0000290

** PROPOSAL**

DATE : February 24, 2017

TO: Michael Lloyd Hauling, Inc.
1601 Rudd Road
Jacksonville, Florida 32220

ATTN: Mr. Michael Lloyd

RE : ***RESIDENCE @ 3553 MECCA STREET***
JACKSONVILLE, FLORIDA

Alachua Environmental Services, Inc. proposes to provide all labor and materials to remove and dispose asbestos containing materials on the above referenced project. The following shall clarify our quotation:

REMOVE AND DISPOSE OF ASBESTOS CONTAINING TRANSITE SIDING (GRAY).
A. E. S., INC. WILL COMPLY WITH ALL LOCAL, STATE AND FEDERAL AND WILL DISPOSE OF WASTE IN AN APPROVED LANDFILL.

A. E. S., INC. WILL CONDUCT WORK FOR THE SUM OF: $3,000.00

NOTE : IF PAYING INVOICE BY CREDIT CARD, THERE WILL BE AN ADDITIONAL 4% ADDED TO COST

Alachua Environmental Services, Inc. would like to thank you for this opportunity to quote this proposal with you. Should you have any questions regarding this proposal, please feel free to give me a call.
Cell contact # 904-334-1527 / Fax # 904-259-6299 Email @ aesinc_othornton@nefcom.net

Sincerely,
ALACHUA ENVIRONMENTAL SERVICES, INC.
Owen E. Thornton

OWEN E. THORNTON
President

OET / kc

Michael Lloyd Hauling, Inc.

1601 Rudd Road
Jacksonville, FL 32220
PH 904-759-1861
FX 904-781-7670
Michaellloydhauling@outlook.com

Date 2/21/17

Mike,
I need to get a C/O for the following:

Address: 3553 Mecca Street
PO# 7A03096
Original Amount: $4,400.00
For WET DEMO
Change Order Amount: $1,250.0

Thank you,
Melissa Lloyd
Michael Lloyd Hauling Inc.

Neighborhoods Department
Municipal Code Compliance Division

MAR 16 2017

AVA HILL

ENVIRONEERING INC.
109 AZALEA POINT DRIVE SOUTH • PONTE VEDRA BEACH • FLORIDA • 32082

February 9, 2017

Mr. Michael Lloyd
Michael Llyod Hauling, Inc.
1601 Rudd Road
Jacksonville, Florida 32220

Reference: One (1) Single Story Structure – Asbestos Demolition Survey – House
3553 Mecca Street
Jacksonville, Florida – JON 5857

Dear Mr. Llyod:

Pursuant to your request an Asbestos Demolition Survey has been performed at the above location for the purpose of identifying asbestos that needs to be removed prior to the planned demolition of the structure. The purpose of the investigation was to visually identify homogenous materials that need to have bulk samples obtained for analysis to determine the presence of Asbestos Containing Building Materials with in the structure. The scope of this survey was limited to the referenced one (1) single story structure in Jacksonville, Florida. The building was inspected for demolition. The facility has one single story structure for demolition, which is constructed with concrete, wood, drywall, chimney mastic, attic insulation, window glazing, texture coat paint, steel and aluminum. There were eight (8) suspected materials that were sampled for Polarized Light Microscopy (PLM) analysis. Based on the visual inspection, it was evident that National Emission Standard for Hazardous Air Pollutants (NESHAP) 40 CFR Part 61 regulated Asbestos Material was found to be present at the facility. The scope of work for this survey included sampling and analysis of suspect homogenous building materials. The asbestos demolition inspection process was initiated on January 26, 2017. Materials must contain greater than 1% asbestos to be regulated. The following recommendations are provided for the material that was found to contain Asbestos Fibers within the referenced structure.

RECOMMENDATIONS

Recommended response actions have been selected for all Asbestos Containing Materials identified by this survey within the facility. Recommendations for response actions, where arrived at, are stated as follows:

FRIABLE ASBESTOS CONTAINING MATERIALS

Friable Asbestos Material means any material containing more than one (1%) percent asbestos, that when dry can be crumbled, pulverized or reduced to powder by hand pressure.

(904) 665-0100 (904) 612-1456 • MOBILE (904) 665-0101• FAX

Friable Asbestos Material was found in the following area:

None.

The above material is considered friable and must be removed by a Certified Florida Asbestos Abatement Contractor prior to any disturbance caused by renovation or demolition of the referenced structure.

CATEGORY I, NON-FRIABLE ASBESTOS MATERIAL

None.

CATEGORY II, NON-FRIABLE ASBESTOS MATERIAL

HM-6 Transite Siding - Gray [15-20% Chrysotile Asbestos - Presumed]

NONREGULATED BY NESHAP; REGULATED BY OSHA

HM-1 Drywall System – Star Pattern – White [<1% Chrysotile Asbestos]
HM-3 Texture Coat Paint – Gray – Exterior [<1% Chrysotile Asbestos]
HM-5 Chimney Mastic – Black [<1% Chrysotile Asbestos]

The preceding materials are considered a Category I or II Non-Friable Material and therefore, under normal circumstances, the Category I material does not need not be removed prior to demolition, because generally these materials do not release significant amounts of Asbestos Fibers, even when damaged.

Category I material must be kept wet to prevent the release of fibers during demolition. The Category I asbestos waste must be placed in a permitted asbestos landfill in accordance with FDEP regulations. Friable asbestos and Category II material must be removed prior to demolition or renovation of the structure. Yet, in the event removal is deemed necessary as a part of renovation all Asbestos Containing Material should be removed by a Florida Licensed Asbestos Contractor. The building materials identified in this asbestos renovation survey were in good condition to significantly damaged at the time of the inspection. The material condition can change over time and will degrade with exposure to water, air movement, physical damage, weather and chemical exposure.

The structure has an address of, 3553 Mecca Street, Jacksonville, Florida. The facility was at one time a house. The facility has one single story structure for demolition.

When implementing the response actions, parties responsible for final selection should remember that actions shall be sufficient to protect HUMAN HEALTH AND THE ENVIRONMENT, but may also be the least burdensome method. Nothing in these recommendations should be construed as PROHIBITING or discouraging removal.

All parties shall comply with all applicable laws, ordinances, rules and regulations of Federal, State and Local Governments and Agencies relating to or affecting the proposed work in whole or in part when implementing any response action associated with the facility.

The following samples are recommended to be further analyzed by the point count method using a positive stop approach.

None.

This asbestos survey shall not be used as a design or specification for the removal of asbestos within the referenced structure.

RECOMMENDATIONS FOR ASBESTOS ABATEMENT: (3553 Mecca Street, Jacksonville, Florida)

The HM-6 transite siding asbestos material must be removed prior to demolition by a Florida Licensed Asbestos Abatement Contractor using wet methods.

The HM-1, HM-3 and HM-5 asbestos materials should be wet demolished or should be removed by an asbestos abatement contractor keeping in mind that the most economical method or least burdensome method can be used. These materials are regulated by one or both of the following regulations: the Occupational Safety and Health Administration (OSHA) Construction Standard for Asbestos found in Title 29 Code of Federal Regulations (CFR) Part 1926.1101 and by the National Emission Standards for Hazardous Air Pollutants (NESHAP) Title 40 CFR Part 61.145.

It has been a pleasure working with you and I look forward to working with you once again in the future. I can be reached at (904) 665-0100 or mobile (904) 612-1456 if you should have any questions.

Respectfully submitted,

Timothy W. Rudolph 2/9/2017

Timothy W. Rudolph, P.E., L.A.C.
Licensed Asbestos Consultant AX 0000058
Asbestos Business License ZA0000243
< MICHAEL LLOYD HAULING-ASBESTOS- SURVEY-JON-5857.doc>

D702494

ROUTINE CHAIN OF CUSTODY FORM **JON 5857**

ENVIRONEERING, INC., 109 Azalea Point Drive South, Ponte Vedra Beach, Florida 32082

To Laboratory: Dove Environmental Laboratory
8910 Miramar Parkway, Suite 200
Miramar, FL 33025

ROUTINE TAT

Customer Information
Company Name: ENVIRONEERING, INC.
Address: 109 Azalea Point Drive South
City, State, Zip: Ponte Vedra Beach, FL 32082
Contact: Mr. Tim Rudolph

Date: 1/26/2017
Phone: (904) 665-0100
Fax: (904) 665-0101
Project: Michael Lloyd Hauling, Inc.
3553 Mecca Street
Jacksonville, Florida
<COC-DOVE-5856-1.XLS>

HOUSE & SHED

Sample #	Sample Type	Sample Location	COLOR/AREA	F/NF
1-1,2&3	BULK	Drywall System - Star Pattere - White	White/Ceiling	NF
2-1	BULK	Window glazinf - White	White/Window	NF
3-1	BULK	Testure Coat Paint - Gray - Exterior	Gray/Walls	NF
4-1	BULK	Attic Insulation - Gray (Mineral Wool)	Gray/Attic	F
5-1	BULK	Chimney Mastic - Black	Black/Chimney	NF
6-1	BULK	Traniste Siding - Gray (Fire)	Gray/Walls	F/NF

ENCLOSURE (1)
ENVIRONEERING, Inc. Ltr Dtd 02/09/17

ASBESTOS - PLM * USE POSITIVE STOP METHOD *

CHAIN OF CUSTODY

CHECK # 2867 Paid

Date/Time	Released by:	Date/Time	Released by:
1/30/17 - 20:00			
	TIM RUDOLPH		

c:\program files\Microsoft office\office\nervin\COC1

Rec By - M. Hosseini
Date/Time - 02/01/17 11:39 am

DOVE ENVIRONMENTAL CORP.
8910 MIRAMAR PARKWAY, SUITE 200 MIRAMAR FL 33025
Tel. (954) 374-9274 Fax: (954) 639-7426

ASBESTOS TEST REPORT

CLIENT : ENVIRONEERING, INC.
ADDRESS: 109 AZALEA POINT DRIVE., SOUTH
PONTE VEDRA BCH FL 32082
PROJECT: JON 5857/ MICHAEL LLOYD HAULING, INC
3553 MECCA STREET JACKSONVILLE, FL
CONSULT: TIM RUDOLPH

PAGE : 1
DATE : 02/02/17
SAMPLE ID : D702494
NVLAP Lab Code: 102053-0

LAB NO. : 01
FRI/HOM : YES/NO LAYERS: 03
DESCRIPTION : DRYWALL SYSTEM - STAR PATTERN - WHITE
<1% CHRY. FOUND UNDER PAINT LAYER
ASBESTOS TYPE: <1% CHRYSOTILE
OTHER FIBERS : 9.5 % CELLULOSE
NON FIBERS : 80% MINERALS 10% PAINT

SAMPLE NO.: 1-1
DATE OF ANALYSIS: 02/02/17

LAB NO. : 02
FRI/HOM : YES/NO LAYERS: 03
DESCRIPTION : DRYWALL SYSTEM - STAR PATTERN - WHITE
<1% CHRY. FOUND UNDER PAINT LAYER
ASBESTOS TYPE: <1% CHRYSOTILE
OTHER FIBERS : 9.5 % CELLULOSE
NON FIBERS : 80% MINERALS 10% PAINT

SAMPLE NO.: 1-2
DATE OF ANALYSIS: 02/02/17

LAB NO. : 03
FRI/HOM : YES/NO LAYERS: 03
DESCRIPTION : DRYWALL SYSTEM - STAR PATTERN - WHITE
<1% CHRY. FOUND UNDER PAINT LAYER
ASBESTOS TYPE: <1% CHRYSOTILE
OTHER FIBERS : 9.5 % CELLULOSE
NON FIBERS : 80% MINERALS 10% PAINT

SAMPLE NO.: 1-3
DATE OF ANALYSIS: 02/02/17

Dove Environmental Corporation is solely responsible for analysis performed on sample content supplied by client and is NVLAP accredited for Method 40 CFR Pt. 736, App. A to Subpart E EPA/600/R-93/116. Measurement Uncertainty information is available by contacting the Laboratory. Laboratory Reports will be kept for a period of three (3) years electronically. Percentages are visually estimated. Point count performed at clients request only. Results relates only to item analyzed. This report should not be reproduced by client or anyone without written permision from Dove Environmental Corporation. All samples will be stored for a period of 1 month. The use of the term NVLAP does not constitute endorsement by NVLAP or any agency of the United States Government. Floor-Tile is non-homogeneous and results only reflect sample content.

Analyst 1

R. Pepe Ramnath, PhD
LABORATORY MANAGER

DOVE ENVIRONMENTAL CORP.
8910 MIRAMAR PARKWAY, SUITE 200 MIRAMAR FL 33025
Tel. (954) 374-9274 Fax: (954) 639-7426

ASBESTOS TEST REPORT

CLIENT : ENVIRONEERING, INC.
ADDRESS: 109 AZALEA POINT DRIVE., SOUTH PONTE VEDRA BCH FL 32082
PROJECT: JON 5857/ MICHAEL LLOYD HAULING, INC 3553 MECCA STREET JACKSONVILLE, FL
CONSULT: TIM RUDOLPH

PAGE : 2
DATE : 02/02/17
SAMPLE ID : D702494
NVLAP Lab Code: 102053-0

LAB NO. : 04
FRI/HOM : NO/NO LAYERS: 02
DESCRIPTION : WINDOW GLAZING - WHITE
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 5% CELLULOSE
NON FIBERS : 55% MINERALS
30% POLYMERS

SAMPLE NO.: 2-1
DATE OF ANALYSIS: 02/02/17
10% PAINT

LAB NO. : 05
FRI/HOM : YES/NO LAYERS: 02
DESCRIPTION : TEXTURE COAT PAINT - GRAY - EXTERIOR
<1% CHRY. THROUGHOUT MATERIAL
ASBESTOS TYPE: <1% CHRYSOTILE
OTHER FIBERS : 9.5 % MINERAL WOOL
NON FIBERS : 80% MINERALS

SAMPLE NO.: 3-1
DATE OF ANALYSIS: 02/02/17
10% PAINT

LAB NO. : 06
FRI/HOM : YES/YES LAYERS: 01
DESCRIPTION : ATTIC INSULATION - GRAY (MINERIAL WOOL)
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 90% CELLULOSE
NON FIBERS : 10% MINERALS

SAMPLE NO.: 4-1
DATE OF ANALYSIS: 02/02/17

Dove Environmental Corporation is solely responsible for analysis performed on sample content supplied by client and is NVLAP accredited for Method 40 CFR Pt. 736, App. E to Subpart E EPA/600/R-93/116. Measurement Uncertainty information is available by contacting the Laboratory. Laboratory Reports will be kept for a period of three (3) years electronically. Percentages are visually estimated. Point count performed at clients request only. Results relates only to item analyzed. This report should not be reproduced by client or anyone without written permission from Dove Environmental Corporation. All samples will be stored for a period of 1 month. The use of the term NVLAP does not constitute endorsement by NVLAP or any agency of the United States Government. Floor-Tile is non-homogeneous and results only reflect sample content.

Analyst 1

R. Pepe Ramnath, PhD
LABORATORY MANAGER

DOVE ENVIRONMENTAL CORP.
8910 MIRAMAR PARKWAY, SUITE 200 MIRAMAR FL 33025
Tel. (954) 374-9274 Fax: (954) 639-7426

ASBESTOS TEST REPORT

CLIENT : ENVIRONEERING, INC.
ADDRESS: 109 AZALEA POINT DRIVE., SOUTH
PONTE VEDRA BCH FL 32082
PROJECT: JON 5857/ MICHAEL LLOYD HAULING, INC
3553 MECCA STREET JACKSONVILLE, FL
CONSULT: TIM RUDOLPH

PAGE : 3
DATE : 02/02/17
SAMPLE ID : D702494
NVLAP Lab Code: 102053-0

LAB NO. : 07
FRI/HOM : NO/YES LAYERS: 01
DESCRIPTION : CHIMNEY MASTIC - BLACK
<1% CHRY. THROUGHOUT MATERIAL
ASBESTOS TYPE: <1% CHRYSOTILE
OTHER FIBERS : 4.5 % CELLULOSE
NON FIBERS : 20% MINERALS

SAMPLE NO.: 5-1
DATE OF ANALYSIS: 02/02/17

75% RESINS

LAB NO. : 08
FRI/HOM : NO/NO LAYERS: 02
DESCRIPTION : TRANSITE SIDING - GRAY (FIRE)
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 1% CELLULOSE
NON FIBERS : 60% MINERALS
30% POLYMERS

SAMPLE NO.: 6-1
DATE OF ANALYSIS: 02/02/17

9% PAINT

Dove Environmental Corporation is solely responsible for analysis performed on sample content supplied by client and is NVLAP accredited for Method 40 CFR Pt. 736, App. E to Subpart E EPA/600/R-93/116. Measurement Uncertainty information is available by contacting the Laboratory. Laboratory Reports will be kept for a period of three (3) years electronically. Percentages are visually estimated. Point count performed at clients request only. Results relates only to item analyzed. This report should not be reproduced by client or anyone without written permision from Dove Environmental Corporation. All samples will be stored for a period of 1 month. The use of the term NVLAP does not constitute endorsement by NVLAP or any agency of the United States Government. Floor-Tile is non-homogeneous and results only reflect sample content.

Analyst 1

R. Pepe Ramnath, PhD
LABORATORY MANAGER

TITLE: DEMO & SITE CLEARANCE OF 40 PROPERTIES BID NO.: CF-0082-15 (MUNICIPAL CODE)		ARWOOD WASTE INC.				AMAN CONSTRUCTION SERVICES, LLC.				MICHAEL LLOYD HAULING, INC			
17	2318 LABELLE STREET, (GARAGE ONLY) DESCRIBED AS; 4-61 16-2S-26E WESTBROOK LOTS 12, 13, BLK 10 (DEMOLITION AND SITE CLEARANCE) R.E. #055988-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITION) (NORTHWEST)	N/A	N/A	N/A	N/A	$ 110.00	$ 3,850.40	$ 3,960.40	$ 8,822.87	$ 225.00	$ 3,150.00	$ 3,375.00	$ 4,630.00
18	7463 LAURA STREET, (SINGLE STORY STRUCTURE) DESCRIBED AS; 6-82 39-1S-26E P I COS S/D PANAMA PARK LOTS 2, 3 BLK 15 (DEMOLITION AND SITE CLEARANCE) R.E. #032837-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITION) (NORTH)	$ 225.00	$ 6,900.00	$ 7,125.00	$ 29,000.00	$ 247.50	$ 7,060.87	$ 7,308.37	$ 16,325.91	$ 225.00	$ 5,275.00	$ 5,500.00	$ 7,500.00
19	2817 MARKET STREET, (MAIN STRUCTURE AND ACCESSORY) DESCRIBED AS; NE1/4 OF NW1/4 PT RECD O/R 1170-91 (DEMOLITION AND SITE CLEARANCE) R.E. #044641-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (URBAN CORE)	$ 425.00	$ 13,500.00	$ 13,925.00	$ 45,900.00	$ 467.50	$ 17,129.97	$ 17,597.47	$ 58,539.15	$ 350.00	$ 12,575.00	$ 12,925.00	$ 15,925.00
20	3553 MECCA STREET, (SINGLE STORY STRUCTURE) DESCRIBED AS; 2-59 04-2S-26E GRAND PARK LOT 3, 4 BLK 15 (DEMOLITION AND SITE CLEARANCE) R.E. #047569-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTHWEST)	$ 325.00	$ 6,900.00	$ 7,225.00	$ 28,900.00	$ 357.50	$ 7,063.89	$ 7,421.39	$ 24,848.09	$ 225.00	$ 4,175.00	$ 4,400.00	$ 5,650.00
21	8521 NEW KINGS ROAD, (MAIN STRUCTURE) DESCRIBED AS; 42-1S-26E I CARTER DONATION PT RECD O/R BK 7412-786 (DEMOLITION AND SITE CLEARANCE) R.E. #039968-0010 (CONTRACTOR MUST SUBMIT A BID FOR COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTHWEST)	$ 425.00	$ 18,900.00	$ 19,325.00	$ 59,900.00	$ 467.50	$ 34,182.06	$ 34,649.56	$ 95,003.79	$ 500.00	$ 22,575.00	$ 23,075.00	$ 48,775.00
22	2561 ORION STREET, (MAIN STRUCTURE AND ACCESSORY STRUCTURE) DESCRIBED AS; 06-097 SEC 3 FRAZEES S/D NORTH RIVERSIDE LOTS 16, 16 BLK 3 O/R BK 3151-985 (DEMOLITION AND SITE CLEARANCE) R.E. #055583-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTHWEST)	$ 425.00	$ 13,900.00	$ 14,325.00	$ 48,900.00	$ 467.50	$ 27,506.05	$ 27,973.55	$ 62,009.31	$ 350.00	$ 12,850.00	$ 13,200.00	$ 15,700.00
23	1145 PALMETTO STREET, (SINGLE STORY STRUCTURE) DESCRIBED AS; 07-2S-27E CAMPBELLS ADDN TO JAX LOT 7 BLOCK 1 (DEMOLITION AND SITE CLEARANCE) R.E. #114178-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (URBAN CORE)	$ 200.00	$ 8,100.00	$ 8,300.00	$ 28,900.00	$ 220.00	$ 12,311.52	$ 12,531.52	$ 27,789.34	$ 225.00	$ 5,175.00	$ 5,400.00	$ 7,400.00
24	6033 PEELER ROAD SOUTH, (SINGLE STORY STRUCTURE) DESCRIBED AS; 28-17 4-2S-27E ARLINGTON HILLS UNIT NO 7-A LOT 44 BLK 22 (DEMOLITION AND SITE CLEARANCE) R.E. #119558-0000 (CONTRACT MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (ARLINGTON)	$ 200.00	$ 6,800.00	$ 7,000.00	$ 27,500.00	$ 220.00	$ 12,331.48	$ 12,551.48	$ 27,833.26	$ 225.00	$ 4,675.00	$ 4,900.00	$ 6,400.00
25	3811 PERRY STREET, (SINGLE STORY STRUCTURE) DESCRIBED AS; 3-4 01-2S-26E .128 OWENS ADDN TO JACKSONVILLE S 1/2 LOT 5 BLK 5 (EX PT RECD O/R 2158-134) (DEMOLITION AND SITE CLEARANCE) R.E. #086541-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTH)	$ 150.00	$ 6,000.00	$ 6,150.00	$ 27,000.00	$ 165.00	$ 8,965.20	$ 9,130.20	$ 30,294.65	$ 225.00	$ 3,850.00	$ 4,075.00	$ 5,325.00
26	3508 PHYLLIS STREET, (SINGLE STORY STRUCTURE) DESCRIBED AS; 6-89 20-2S-26E .29 S/D LOT 12 BLK 71 EDGEWOOS LOT 15, 16, N 37.5FT OF LOTS 17, 18, N 37.5FT OF E 1/2 LOT 19 (DEMOLITION AND SITE CLEARANCE) R.E. #078931-0000 (CONTRACTOR MUST A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTHWEST)	$ 150.00	$ 5,600.00	$ 5,750.00	$ 24,900.00	$ 165.00	$ 8,968.83	$ 9,133.83	$ 30,306.63	$ 225.00	$ 3,825.00	$ 4,050.00	$ 5,300.00
27	5367 RIVER FOREST DRIVE, (SINGLE STORY STRUCTURE) DESCRIBED AS; 21-47 16-2S-27E RIVER FOREST UNIT NO 1 LOT 7 BLK 3 (DEMOLITION AND SITE CLEARANCE) R.E. #128416-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITION) (ARLINGTON)	$ 225.00	$ 6,800.00	$ 7,025.00	$ 29,000.00	$ 247.50	$ 11,549.16	$ 11,796.66	$ 26,200.16	$ 225.00	$ 4,875.00	$ 5,100.00	$ 6,600.00
28	1319 RUSHING STREET, (SINGLE STORY STRUCTURE) DESCRIBED AS; 1-127 10-2S-26E .09 MILLER & DEVANES S/D LOT 17, S 33FT LOT 18 BLK 1 (DEMOLITION AND SITE CLEARANCE) R.E. #052783-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITION) (NORTHWEST)	$ 225.00	$ 5,800.00	$ 6,025.00	$ 26,000.00	$ 247.50	$ 5,721.73	$ 5,969.23	$ 13,379.80	$ 225.00	$ 4,175.00	$ 4,400.00	$ 5,900.00
29	1349 RUSHING STREET (MAIN STRUCTURE AND ACCESSORY) DESCRIBED AS; 10-2S-26E MILLER & DEVANES S/D PT LOT 9 N 2FT LOT 24, LOT 25 BLK 1 O/R BK 399-210 (DEMOLITION AND SITE CLEARANCE) R.E. #052790-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITION) (NORTHWEST)	$ 150.00	$ 5,900.00	$ 6,050.00	$ 25,900.00	$ 165.00	$ 6,622.74	$ 6,787.74	$ 15,098.02	$ 225.00	$ 3,875.00	$ 4,100.00	$ 5,350.00
30	2146 THELMA STREET, (SINGLE STORY STRUCTURE) DESCRIBED AS; 4-10 08-2S-27E SUTHERLAND PLACE LOT L BLK 19 (DEMOLITION AND SITE CLEARANCE) R.E. #115504-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (URBAN CORE)	$ 325.00	$ 6,400.00	$ 6,725.00	$ 25,500.00	$ 357.50	$ 16,247.28	$ 16,604.78	$ 55,153.26	$ 225.00	$ 4,000.00	$ 4,225.00	$ 5,475.00
31	6042 TRANSYLVANIA, (ACCESSORY STRUCTURE ONLY) DESCRIBED AS; 18-4 07-3S-26E LYNNWOOD S/D PT SE 1/4 OF SW 1/4 LOT12 BLK 4 (DEMOLITION AND SITE CLEARANCE) R.E. #097357-0000(CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (SOUTHWEST)	$ 150.00	$ 5,400.00	$ 5,550.00	$ 25,000.00	$ 165.00	$ 3,845.56	$ 4,010.56	$ 8,988.22	$ 175.00	$ 2,800.00	$ 2,975.00	$ 3,975.00
32	1648 TYLER STREET, (MAIN STRUCTURE), DESCRIBED AS; 6-27 10-2S-26E VANCES S/D PT LOT 4 BLK 6 (DEMOLITION AND SITE CLEARANCE) R.E. #052659-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITON) (URBAN CORE)	$ 425.00	$ 7,900.00	$ 8,325.00	$ 37,900.00	$ 467.50	$ 12,159.50	$ 12,627.00	$ 42,136.60	$ 350.00	$ 14,375.00	$ 14,725.00	$ 17,225.00

SUBJECT: **DEMO & SITE CLEARANCE OF FORTY (40) PROPERTIES**

BID# CF-0082-15 OPEN DATE: **2015-02-25**

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT:
CONSTRUCTION FIXED

AGENCY: **MUNICIPAL CODE**

BASIS OF AWARD: **BY ITEM TO THE LOWEST RESPONSIVE, RESPONSIBLE BIDDER**

NUMBER OF BIDS INVITED 7 NUMBER RECEIVED 5 OTHER 0

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:

Recommend approval to reject Best-Tec Asbestos Abatement, Inc., for not being pre-qualified on the city's pre-qualified vendor's list under the demolition category at time of bid opening.

Recommend approval to award to the lowest responsive, responsible bidder(s) as follows: Michael Lloyd Hauling, Inc. bid item(s) 1, 2, 4, 6, 7, 8, 9, 11, 12, 14, 16, 17, 18, 20, 22, 24, 25, 26, 27, 28, 29, 30, 31, 33, 36, 37, 38, 39 and 40 in the amount of $137,981.00; Arwood, Inc. bid item 32 in the amount of $8,325.00; and Hager Construction Company bid item(s) 19, 21, and 35 in the amount of $38,281.00. Total award not-to-exceed $184,587.00.

Item(s) 3, 5, 10, 13, 15, 23 and 34 will not be awarded at this time.

Funding for this award to be encumbered by account: ERCC011CP-03410 to be executed by Purchase Order(s).

Attachments: Recommendation Memo, Bid Tabulation Sheet, Vendor Rejection Letter, Terms & Conditions

BUYER: Marilyn Laidler
MARILYN LAIDLER

RESPECTFULLY SUBMITTED: _____
GREGORY PEASE, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: **Robert Prado, Chief, Municipal Code Compliance Division**

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING 3 MEMBERS DISAPPROVING _____ DATE: 03/26/15

_____ OTHER: _____

_____

_____

ACTION OF AWARDING AUTHORITY DATE: 3/26/15

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

Cleveland Ferguson III
Deputy Chief Administrative Officer
For Mayor Alvin Brown
Under Authority of
Executive Order No. 2015-01

FORM GB-108, Revised 12/2007

QWS3270X 3/24/2017 8:56 AM
FAML6350 V5.1 ** NW COJ FAMIS PRODUCTION ** 03/24/2017
LINK TO: ACCOUNT SUMMARY INQUIRY 8:55 AM

FISCAL MO/YEAR : 06 2017 CURRENCY CODE :
INDEX CODE : ERCD1N1FR FORECLOSED PROPERTY REGISTRY-HOUSING SER
SUBOBJECT : 03410 CONTRACTUAL SERVICES
PROJECT :
PROJECT DETAIL :
GRANT :
GRANT DETAIL :
USER CODE :

S	MAR 2017	ANNUAL BALANCE	ALL YEARS BALANCE
ESTIMATED REVENUES	.00	.00	.00
REVENUES	.00	.00	.00
UNREALIZED REVENUES	.00	.00	.00
BUDGET	.00	1,115,930.00	1,115,930.00
EXPENDITURES	64,100.00	80,379.00	80,379.00
ENCUMBRANCES	-8,471.80	332,292.20	332,292.20
PRE-ENCUMBRANCES	-19,643.20	.00	.00
REMAINING BALANCE	-35,985.00	703,258.80	703,258.80

F1-HELP F2-SELECT F4-PRIOR F5-NEXT
F9-LINK F10-PRIOR-MO F11-NEXT-MO
G005 - PRIOR RECORD DISPLAYED