SUBJECT: **DEMO & SITE CLEARANCE OF 44 PROPERTIES**

BID# CF-0053-17 OPEN DATE: **2016-12-07**

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT:
CONSTRUCTION FIXED

AGENCY: **MUNICIPAL CODE**

BASIS OF AWARD: **BY ITEM TO THE LOWEST RESPONSIVE, RESPONSIBLE BIDDER**

NUMBER OF BIDS INVITED 6 NUMBER RECEIVED 4 OTHER 0

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:

Item #34 was awarded to ERS Corp on 12/22/16 in the amount of $6,212.50 which included $275.00 cost of asbestos survey as required by bid specifications. The performed asbestos survey requires an asbestos abatement be performed prior to demolition. In accordance with the specifications, the awarded contractor solicited three quotes for asbestos abatement from the following companies:
1) Jensafe Env- $5,600.00; 2) ELS Abatement & Construction- $7,575.00, and; 3) Bradco Env- $9,500.00

Recommend approval to increase award for Item #34 to ERS Corp, in the amount of $5,600.00 for the asbestos abatement. Total award amount for Item #34 not-to-exceed $11,812.50.

This award is to be funded by account: ERCD1N1FR-03410 to be executed by Purchase Order/Change Order.

Attachments: Recommendation Memo, Change Order, Vendor Quotes, Asbestos Report, Previous Award

BUYER: Marilyn Laidler
MARILYN LAIDLER

RESPECTFULLY SUBMITTED: _____
GREGORY PEASE, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: **Bryan Mosier, Chief, Municipal Code Compliance Division**

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING _____ MEMBERS DISAPPROVING _____ DATE: _____

_____ _____ OTHER: _____

_____ _____

_____ _____

ACTION OF AWARDING AUTHORITY DATE: _____

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

FORM GB-108, Revised 12/2007

City of Jacksonville, Florida

ONE CITY. ONE JACKSONVILLE.

Lenny Curry, Mayor

Municipal Code Compliance Division
Ed Ball Building
214 N. Hogan Street, 7th Floor
Jacksonville, Florida 32202

August 17, 2017

M E M O R A N D U M

TO: Gregory Pease, Division Chief
Procurement Division

FROM: Bryan Mosier, Division Chief
Municipal Code Compliance Division

RE: **Change order request for item #34 on CF-0053-17**

The survey of the condemned structure at 1435 E. 14th St. revealed asbestos in the transite siding - gray and in the roof paint – silver, which must be removed by an asbestos abatement contractor prior to demolition.

I recommend approval of the change order request submitted by ERS in the amount of $5,600.00 (reference purchase order # 7A08017)

Contractor	Item Number	Amount
ERS	34	$5,600.00

Funding Source: ERCD1N1FR/03410

BM/ds

ERS Corp.

PROPOSAL

Prepared for:
COJ- Municipal Code Compliance Division
Neighborhoods Department
214 N Hogan St., 7th Floor
Jacksonville, FL 32202

Proposal No: 17544_CO1
Date 8/11/2017
Phone: 904-255-7015
Fax: 904-255-8920
E-Mail: dsteele@coj.net

Attention: Mr. Steele

RE: 1435 E 14th St., RE: 26718-0000 (Case No. 2016-28437)
Current Purchase Order No. PO7A08017

Request for Change Order #1:

Original Contract Amount.....$6,212.50

Add Abatement activities because of Asbestos Contained Materials.....$5,600.00

We appreciate the opportunity to submit this proposal. If you have any questions or require additional information, please contact John Anderson.

Submitted by:
John Anderson
President – ERS Corp.

JENSAFE ENVIRONMENTAL

"Serving All Your Environmental Needs"

Ph: 904-695-1424
Fx: 904-695-1425

610-3 N. Lane Avenue
Jacksonville, FL 32254

August 2, 2017

ERS
760 Talleyrand Ave
Suite 200
Jacksonville, FL 32202
Email: j.anderson@ersfl.com

Attention: John Anderson
RE: Asbestos Abatement on 2 Story House and Shed at 1435 East 14th Street.

We are pleased to provide this quote for your consideration on the project as referenced above.

Scope of Work

- Mobilize all equipment and materials to site listed above.
- Remove and dispose approximately 2,200 S/F of transite siding.
- Remove and dispose approximately 1550 S/F of metal roof on house and shed.
- The wet method will be utilized for the removal of asbestos containing materials.
- All ACM debris will be disposed of at and approved landfill.
- Employees will use personal protective equipment.
- All work will be performed during normal working hours.

The total cost of this project will be Five Thousand Six Hundred Dollars ($5,600.00).

CLARIFICATIONS:

1. Our proposal includes two (2) million dollar, per occurrence, one million dollar umbrella, per aggregate liability insurance coverage.
2. Work to be completed under current Federal, State, and Local agency regulation, which includes the filing of all notification and permits. Permit fees will be an additional charge, if applicable.

3. Asbestos material removed from the job site will be disposed of in an EPA authorized landfill and the disposal receipt provided to the customer.
4. Customer to provide access for asbestos contractor's vehicles and equipment near the immediate work area.
5. Ten working day notification is required / is not required / will be determined by Duval County Regulatory and Environmental, Air Quality Division.
6. This proposal is based upon 1 mobilization to the project site.
7. Customer to provide water and electric to job site.
8. Customer the responsible for any items saved prior to Asbestos Abatement.
9. Not responsible for damages during abatement.

We appreciate the opportunity to provide this quote to you on this project and look forward to working with you. If you have any questions or require further assistance, please do not hesitate to call me at (904) 695-1424.

Sincerely,

_____ _____

Acceptance of Proposal Date

Eli Jensen

ELS Abatement & Construction, Inc.
1408 St. Johns Bluff Rd. N.
Jacksonville, FL 32225

August 3, 2017

Mr. John Anderson
ERS Corp.
760 Talleyrand Ave.
Jacksonville, Fl. 32202

Re: Asbestos Abatement at property 1435 East 14th St. Jacksonville, FL.

PROPOSAL:

ELS is pleased to submit a proposal to perform the asbestos abatement of the ACM transite siding and the silver paint that is located on the roof of the home and the entire shed (separate structure). The building materials containing the silver paint will be removed and disposed of as asbestos. The below is included.

- Labor, supplies and equipment including manlift
- Wet method
- In accordance with 29 CFR 1926.1101
- All asbestos contained materials will be disposed of at Trail Ridge Landfill via appropriate manifest

Price: **$7,575.00**

(Seven thousand five hundred seventy-five dollars and 00/100 cents)

Any alterations or deviations from above specification involving extra cost with be executed only upon written order, and will become an Extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control.

Respectfully Submitted by: ELS Abatement & Construction, Inc.

Proposal Accepted by: _____ Date: _____

_____ Date: _____

BRADCO ENVIRONMENTAL

5810 Stuart Avenue, Jacksonville FL 32254 904 334-3517

August 8, 2017

PROPOSAL

To: ERS
760 Talleyrand Ave.
Jacksonville, FL 32202
Attn: John Anderson

RE: 1435 East 14th St.

Bradco Environmental proposes to furnish all labor, material, trucking, disposal and applicable notifications for the project listed above. This Material is friable and must be removed by a licensed Asbestos Contractor. Removal is performed by a licensed Asbestos Contractor in accordance with EPA and OSHA regulations.

- Removal of ACM roof
- Removal of ACM siding
- Price includes trucking and disposal by EPA approved landfill facility.

Total Price $9500

Jerry F Bradley, President

PAYMENT FOR WORK PERFORMED UPON RECEIPT OF INVOICE.

ACCEPTANCE OF PROPOSAL

AUTHORIZED PARTY:_____ DATE: _____

THANK YOU FOR THE OPPORTUNITY TO DO BUSINESS

ENVIRONEERING INC.
109 AZALEA POINT DRIVE SOUTH • PONTE VEDRA BEACH • FLORIDA • 32082

July 19, 2017

Mr. John Anderson, President
E. R. S. Corp
760 Talleyrand Avenue
Jacksonville, Florida 32202

Reference: One (1) Single & One (1) Two Story Structures – Asbestos Demolition Survey – House & Accessory or Auxiliary Structure. 1435 East 14th Street Jacksonville, Florida – JON 6067

Dear Mr. Anderson:

Pursuant to your request an Asbestos Demolition Survey has been performed at the above location for the purpose of identifying asbestos that needs to be removed prior to the planned demolition of the structures. The purpose of the investigation was to visually identify homogenous materials that need to have bulk samples obtained for analysis to determine the presence of Asbestos Containing Building Materials with in the structures. The scope of this survey was limited to the referenced one (1) single and one (1) two story structure in Jacksonville, Florida. The buildings were inspected for demolition. The facility has one (1) single and one (1) two story structure for demolition, which are constructed with concrete, wood, drywall, plaster, window glazing, transite siding, roof paint steel and aluminum. There were six (6) suspected materials that were sampled for Polarized Light Microscopy (PLM) analysis. Based on the visual inspection, it was evident that National Emission Standard for Hazardous Air Pollutants (NESHAP) 40 CFR Part 61 regulated Asbestos Material was found to be present at the facility. The scope of work for this survey included sampling and analysis of suspect homogenous building materials. The asbestos demolition inspection process was initiated on July 12, 2017. Materials must contain greater than 1% asbestos to be regulated. The following recommendations are provided for the material that was found to contain Asbestos Fibers within the referenced structure.

RECOMMENDATIONS

Recommended response actions have been selected for all Asbestos Containing Materials identified by this survey within the facility. Recommendations for response actions, where arrived at, are stated as follows:

FRIABLE ASBESTOS CONTAINING MATERIALS

Friable Asbestos Material means any material containing more than one (1%) percent asbestos, that when dry can be crumbled, pulverized or reduced to powder by hand pressure.

(904) 665-0100 (904) 612-1456 • MOBILE (904) 665-0101 • FAX

Friable Asbestos Material was found in the following area:

None.

The above material is considered friable and must be removed by a Certified Florida Asbestos Abatement Contractor prior to any disturbance caused by renovation or demolition of the referenced structure.

CATEGORY I, NON-FRIABLE ASBESTOS MATERIAL

None.

CATEGORY II, NON-FRIABLE ASBESTOS MATERIAL

HM-5 Transite Siding - Gray [15% Chrysotile Asbestos] (House)
HM-6 Roof Paint - Silver [5% Chrysotile Asbestos]

NONREGULATED BY NESHAP; REGULATED BY OSHA

None.

The preceding materials are considered a Category I or II Non-Friable Material and therefore, under normal circumstances, the Category I material does not need not be removed prior to demolition, because generally these materials do not release significant amounts of Asbestos Fibers, even when damaged.

Category I material must be kept wet to prevent the release of fibers during demolition. The Category I asbestos waste must be placed in a permitted asbestos landfill in accordance with FDEP regulations. Friable asbestos and Category II material must be removed prior to demolition or renovation of the structure. Yet, in the event removal is deemed necessary as a part of renovation all Asbestos Containing Material should be removed by a Florida Licensed Asbestos Contractor. The building materials identified in this asbestos renovation survey were in good condition to significantly damaged at the time of the inspection. The material condition can change over time and will degrade with exposure to water, air movement, physical damage, weather and chemical exposure.

The structures have an address of, 1435 East 14th Street, Jacksonville, Florida. The facility was at one time a house and accessory or auxiliary structure. The facility has one (1) single and one (1) two story structure for demolition.

When implementing the response actions, parties responsible for final selection should remember that actions shall be sufficient to protect HUMAN HEALTH AND THE ENVIRONMENT, but may also be the least burdensome method. Nothing in these recommendations should be construed as PROHIBITING or discouraging removal.

All parties shall comply with all applicable laws, ordinances, rules and regulations of Federal, State and Local Governments and Agencies relating to or affecting the proposed work in whole or in part when implementing any response action associated with the facility.

The following samples are recommended to be further analyzed by the point count method using a positive stop approach.

None.

This asbestos survey shall not be used as a design or specification for the removal of asbestos within the referenced structure.

RECOMMENDATIONS FOR ASBESTOS ABATEMENT: (1435 East 14th Street, Jacksonville, Florida)

The HM-5 Transite Siding – Gray and the HM-6 Roof Paint – Silver must be removed by an asbestos abatement contractor prior to demolition of the structure.

These material are regulated by both of the following regulations: the Occupational Safety and Health Administration (OSHA) Construction Standard for Asbestos found in Title 29 Code of Federal Regulations (CFR) Part 1926.1101 and by the National Emission Standards for Hazardous Air Pollutants (NESHAP) Title 40 CFR Part 61.145.

It has been a pleasure working with you and I look forward to working with you once again in the future. I can be reached at (904) 665-0100 or mobile (904) 612-1456 if you should have any questions.

Respectfully submitted,

7/19/2017

Timothy W. Rudolph, P.E., L.A.C.
Licensed Asbestos Consultant AX 0000058
Asbestos Business License ZA0000243
< ERS CORP-ASBESTOS- SURVEY-JON-6067.doc>

D707608.

ROUTINE **CHAIN OF CUSTODY FORM** **JON 6067**

ENVIRONEERING, INC., 109 Azalea Point Drive South, Ponte Vedra Beach, Florida 32082

To Laboratory: Dove Environmental Laboratory
8910 Miramar Parkway, Suite 200
Miramar, FL 33025

ROUTINE TAT

Customer Information
Company Name: ENVIRONEERING, INC.
Address: 109 Azalea Point Drive South
City, State, Zip: Ponte Vedra Beach, FL 32082
Contact: Mr. Tim Rudolph

Date: 7/12/2017
Phone: (904) 665-0100
Fax: (904) 665-0101
Project: E R S, CORP
1435 East 14th Street
Jacksonville, Florida
<COC-DOVE-6063-1.XLS>

HOUSE TRAILER

Sample #	Sample Type	Sample Location	COLOR/AREA	F/NF
1-1	BULK	Drywall System - White	White/Walls/Ceilings	NF
2-1	BULK	Plaster - Two coats - White over Gray with Wood Lathe	White/Walls/Ceilings	NF
3-1	BULK	1'X1' Vinyl Floor Tile (VFT) White with Yellow Mastic (Bathroom)	White/Floor	NF
4-1	BULK	Window Glazing - White	White/Window	NF
5-1	BULK	Transite - Gray	Gray/Walls	NF
6-1	BULK	Roof Paint - Silver (Metal Roof House & Shed)	Silver/Roof	NF

[redacted]

ENCLOSURE (1)
Environeering, Inc. Ltr Dtd 07/19/2017

ASBESTOS - PLM * USE POSITIVE STOP METHOD *

CHAIN OF CUSTODY **CHECK #**

Date/Time	Released by:	Date/Time	Released by:
7/12/2017- 20:00	TIM RUDOLPH		

Rec By- D. Hossain
7-17-17 @ ~~12:49pm~~ AM. 12:49pm

c:\program files\Microsoft office\office\mervin\COC1

DOVE ENVIRONMENTAL CORP.
8910 MIRAMAR PARKWAY, SUITE 200 MIRAMAR FL 33025
Tel. (954) 374-9274 Fax: (954) 639-7426

ASBESTOS TEST REPORT

CLIENT : ENVIRONEERING, INC.
ADDRESS: 109 AZALEA POINT DRIVE., SOUTH
PONTE VEDRA BCH FL 32082
PROJECT: ERS, CORP.//JON 6067
1435 EAST 14TH ST. JACKSONVILLE, FL
CONSULT: TIM RUDOLPH

PAGE : 1
DATE : 07/18/17
SAMPLE ID : D707608
NVLAP Lab Code: 102053-0

LAB NO. : 01 SAMPLE NO.: 1-1
FRI/HOM : YES/NO LAYERS: 03 DATE OF ANALYSIS: 07/18/17
DESCRIPTION : DRYWALL SYSTEM-WHITE
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 20% CELLULOSE 10% FIBER-GLASS
NON FIBERS : 60% MINERALS 10% PAINT

LAB NO. : 02 SAMPLE NO.: 2-1
FRI/HOM : NO/NO LAYERS: 04 DATE OF ANALYSIS: 07/18/17
DESCRIPTION : PLASTER-TWO COATS-WHITE OVER GRAY
WITH WOOD LATHE
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 20% CELLULOSE
NON FIBERS : 40% MINERALS 10% PAINT
30% POLYMERS

LAB NO. : 03 SAMPLE NO.: 3-1
FRI/HOM : NO/NO LAYERS: 02 DATE OF ANALYSIS: 07/18/17
DESCRIPTION : 1'X1' VFT WHITE WITH YELLOW MASTIC
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 2% CELLULOSE
NON FIBERS : 58% MINERALS 10% PAINT
30% POLYMERS

Dove Environmental Corporation is solely responsible for analysis performed on sample content supplied by client and is NVLAP accredited for Method 40 CFR Pt. 736, App. E to Subpart E EPA/600/R-93/116. Measurement Uncertainty information is available by contacting the Laboratory. Laboratory Reports will be kept for a period of three (3) years electronically. Percentages are visually estimated. Point count performed at clients request only. Results relates only to item analyzed. This report should not be reproduced by client or anyone without written permision from Dove Environmental Corporation. All samples will be stored for a period of 1 month. The use of the term NVLAP does not constitute endorsement by NVLAP or any agency of the United States Government. Floor-Tile is non-homogeneous and results only reflect sample content.

Analyst 1

R. Pepe Ramnath, PhD
LABORATORY MANAGER

DOVE ENVIRONMENTAL CORP.
8910 MIRAMAR PARKWAY, SUITE 200 MIRAMAR FL 33025
Tel. (954) 374-9274 Fax: (954) 639-7426

ASBESTOS TEST REPORT

CLIENT : ENVIRONEERING, INC.
ADDRESS: 109 AZALEA POINT DRIVE., SOUTH
PONTE VEDRA BCH FL 32082
PROJECT: ERS, CORP.//JON 6067
1435 EAST 14TH ST. JACKSONVILLE, FL
CONSULT: TIM RUDOLPH

PAGE : 2
DATE : 07/18/17
SAMPLE ID : D707608
NVLAP Lab Code: 102053-0

LAB NO. : 04 SAMPLE NO.: 4-1
FRI/HOM : NO/NO LAYERS: 02 DATE OF ANALYSIS: 07/18/17
DESCRIPTION : WINDOW GLAZING-WHITE
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 5% CELLULOSE
NON FIBERS : 55% MINERALS 10% PAINT
30% POLYMERS

LAB NO. : 05 SAMPLE NO.: 5-1
FRI/HOM : NO/YES LAYERS: 01 DATE OF ANALYSIS: 07/18/17
DESCRIPTION : TTRANSITE-GRAY
(15% CHRY FOUND THROUGHOUT MATERIAL)
ASBESTOS TYPE: 15% CHRYSOTILE
OTHER FIBERS : 5% CELLULOSE
NON FIBERS : 40% MINERALS 10% PAINT
30% POLYMERS

LAB NO. : 06 SAMPLE NO.: 6-1
FRI/HOM : YES/YES LAYERS: 01 DATE OF ANALYSIS: 07/18/17
DESCRIPTION : ROOF PAINT-SILVER
ASBESTOS TYPE: 5% CHRYSOTILE
OTHER FIBERS : 5% CELLULOSE
NON FIBERS : 20% MINERALS 70% PAINT

Dove Environmental Corporation is solely responsible for analysis performed on sample content supplied by client and is NVLAP accredited for Method 40 CFR Pt. 736, App. E to Subpart E EPA/600/R-93/116. Measurement Uncertainty information is available by contacting the Laboratory. Laboratory Reports will be kept for a period of three (3) years electronically. Percentages are visually estimated. Point count performed at clients request only. Results relates only to item analyzed. This report should not be reproduced by client or anyone without written permision from Dove Environmental Corporation. All samples will be stored for a period of 1 month. The use of the term NVLAP does not constitute endorsement by NVLAP or any agency of the United States Government. Floor-Tile is non-homogeneous and results only reflect sample content.

Analyst 1

R. Pepe Ramnath, PhD
LABORATORY MANAGER

TITLE: DEMO & SITE CLEARANCE OF 44 PROPERTIES BID NO.: CF-0053-17 (MUNICIPAL CODE)		P & G LAND CLEARING, INC.				ENVIRONMENTAL REMEDIATION				ARWOOD WASTE, INC.			
24	**8975 2ND AVENUE,** (SINGLE FAMILY) DESCRIBED AS; 4-38 40-1S-26E ARMSTRONGS S/D RIVERVIEW LOTS 23,24 BLK 96 (DEMOLITION AND SITE CLEARANCE) R.E. #036196-0000 (CONTRACT MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTH)	$ 275.00	$ 4,875.00	$ 5,150.00	$ 3,000.00	$ 275.00	$ 3,697.50	$ 3,972.50	$ 4,972.50	$ 450.00	$ 6,900.00	$ 7,350.00	$ 25,500.00
25	**3144 N 3RD ST CR** (SINGLE FAMILY) DESCRIBED AS; 22-7 08-2S-26E WESTWOOD PARK LOT 18 BLK 3 (DEMOLITION AND SITE CLEARANCE) R.E. #050193-0000 (CONTRACT MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTHWEST)	$ 275.00	$ 5,275.00	$ 5,550.00	$ 3,000.00	$ 275.00	$ 2,900.00	$ 3,175.00	$ 4,175.00	$ 450.00	$ 5,700.00	$ 6,150.00	$ 24,900.00
26	**8809 3RD AVENUE** (SINGLE FAMILY) DESCRIBED AS;14-16 40-1S-26E .156 ARMSTRONG ACRES UNIT NO 1 PT TRACT 5 RECD O/R 13420-1957 (DEMOLITION AND SITE CLEARANCE) R.E. #036397-0000 (CONTRACTOR MUST A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTH)	$ 275.00	$ 4,925.00	$ 5,200.00	$ 3,000.00	$ 275.00	$ 3,210.00	$ 3,485.00	$ 4,485.00	$ 450.00	$ 6,500.00	$ 6,950.00	$ 29,000.00
27	**9005 4TH AVENUE,** (SINGLE FAMILY) DESCRIBED AS; 4-38 40-1S-26E ARMSTRONGS S/D RIVERVIEW LOT 13 BLK 81 (DEMOLITION AND SITE CLEARANCE) R.E. #036099-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITION)(NORTH)	$ 275.00	$ 5,875.00	$ 6,150.00	$ 3,000.00	$ 275.00	$ 4,000.00	$ 4,275.00	$ 5,275.00	$ 450.00	$ 7,100.00	$ 7,550.00	$ 31,500.00
28	**2838 W 8TH STREET** (SINGLE FAMILY & ACCESSORY) DESCRIBED AS;5-41 08-2S-26E MELSONS ADDN TO JAX LOT 6, PT CLOSED ALLEY BLK 40 (DEMOLITION AND SITE CLEARANCE) R.E. #048607-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITION)(NORTHWEST)	$ 275.00	$ 5,725.00	$ 6,000.00	$ 3,000.00	$ 275.00	$ 3,856.25	$ 4,131.25	$ 5,131.25	$ 450.00	$ 6,500.00	$ 6,950.00	$ 29,900.00
29	**1612 W 10TH STREET** (MAIN STRUCTURE AND ACCESSORY) DESCRIBED AS; 1-58 10-2S-26E MIMSBURG E 25FT LOT 2 & W 40FT LOTS 3,4 BLK 11 (DEMOLITION AND SITE CLEARANCE) R.E. #052297-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITION) (URBAN CORE)	$ 475.00	$ 6,325.00	$ 6,800.00	$ 3,000.00	$ 275.00	$ 4,712.50	$ 4,987.50	$ 5,937.50	N/A	N/A	N/A	N/A
30	**1045 E 12TH STREET** (SINGLE FAMILY) DESCRIBED AS; 07-2S-27E RICHARDSONS S/D N 1/2 OF NW 1/4 LOT 40 O/R BK 4203-231 (DEMOLITION AND SITE CLEARANCE) R.E. #115039-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (URBAN CORE)	$ 275.00	$ 6,875.00	$ 7,150.00	$ 3,000.00	$ 275.00	$ 5,256.25	$ 5,531.25	$ 6,531.25	$ 450.00	$ 7,500.00	$ 7,950.00	$ 29,000.00
31	**1137 E 12TH STREET,** (SINGLE FAMILY) DESCRIBED AS; 1-117 07-2S-27E CORWINS ADDN TO CAMPBELLS ADDN TO JAX LOTS 1,2 BLK F (DEMOLITION AND SITE CLEARANCE) R.E. #114922-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (URBAN CORE)	$ 275.00	$ 4,775.00	$ 5,050.00	$ 3,000.00	$ 275.00	$ 4,353.13	$ 4,628.13	$ 5,628.13	$ 450.00	$ 6,500.00	$ 6,950.00	$ 27,000.00
32	**1243 E 13TH STREET** (SINGLE FAMILY) DESCRIBED AS;2-8 06-2S-27E CLARKSONS ADDN TO EAST SPRINGFIELD LOT 7 BLK 4 (DEMOLITION AND SITE CLEARANCE) R.E. #113712-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (URBAN CORE)	$ 275.00	$ 4,975.00	$ 5,250.00	$ 3,000.00	$ 275.00	$ 3,675.00	$ 3,950.00	$ 4,950.00	$ 400.00	$ 5,800.00	$ 6,200.00	$ 25,500.00
33	**1610 E 13TH STREET,** (SINGLE FAMILY), DESCRIBED AS;6-48 08-2S-27E THOMPSONS ADDN TO EAST SPRINGFIELD LOTS 7, 8 BLK 20 (DEMOLITION AND SITE CLEARANCE) R.E. #131944-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITON) (URBAN CORE)	$ 275.00	$ 5,775.00	$ 6,050.00	$ 3,000.00	$ 275.00	$ 5,872.50	$ 6,147.50	$ 7,147.50	N/A	N/A	N/A	N/A
34	**1435 E 14TH STREET,** (SINGLE FAMILY & ACCESSORY) DESCRIBED AS; 5-4 06-2S-27E HILL INVESTMENT COS S/D PT LOT 9 BLK C LONG BRANCH LOT 20 (DEMOLITION AND SITE CLEARANCE) R.E. #131997-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (URBAN CORE)	$ 475.00	$ 8,775.00	$ 9,250.00	$ 5,000.00	$ 275.00	$ 5,937.50	$ 6,212.50	$ 7,212.50	N/A	N/A	N/A	N/A

SUBJECT: **DEMO & SITE CLEARANCE OF 44 PROPERTIES**

BID# CF-0053-17 OPEN DATE: **2016-12-07**

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT:
CONSTRUCTION FIXED

AGENCY: **MUNICIPAL CODE**

BASIS OF AWARD: **BY ITEM TO THE LOWEST RESPONSIVE, RESPONSIBLE BIDDER**

NUMBER OF BIDS INVITED 6 NUMBER RECEIVED 4 OTHER 0

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:

Recommend approval of award to the lowest responsive, responsible bidder(s) as follows: Environmental Remediation, bid item(s): 1, 2, 3, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 24, 25, 26, 27, 28, 29, 30, 31, 32, 34, 38, 39, 41, 42 and 43 in the amount of $165,583.89; P & G Land Clearing, Inc., bid item(s), 4, 23, 33, 35, 36, 37, 40 and 44 in the amount of $37,200.00. Total award amount not-to-exceed $202,783.89.

Item 16 will not be awarded at this time.

This award to be funded by account: ERCD1N1FR-03410 to be executed by Purchase Order(s).

Attachments: Recommendation Memo, Bid Tabulation Sheet, Terms & Conditions

BUYER: Marilyn Laidler
MARILYN LAIDLER

RESPECTFULLY SUBMITTED: Greg Pease
GREGORY PEASE, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: **Bryan Mosier, Chief, Municipal Code Compliance Division**

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)

ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING 3 MEMBERS DISAPPROVING Ø DATE: 12/22/16

Teresa R Eilmes

OTHER:

ACTION OF AWARDING AUTHORITY DATE: 12/22/16

APPROVED ✓ DISAPPROVED

OTHER

SIGNATURE OF AUTHENTICATION

Sam E. Mousa
Chief Administrative Officer
For: Mayor Lenny Curry
Under Authority of:
Executive Order No. 2015-05

FORM GB-108, Revised 12/2007

QWS3270X 8/21/2017 9:20 AM
FAML6350 V5.1 ** NW COJ FAMIS PRODUCTION ** 08/21/2017
LINK TO: ACCOUNT SUMMARY INQUIRY 9:20 AM

FISCAL MO/YEAR : 11 2017 CURRENCY CODE :
INDEX CODE : ERCD1N1FR FORECLOSED PROPERTY REGISTRY-HOUSING SER
SUBOBJECT : 03410 CONTRACTUAL SERVICES
PROJECT :
PROJECT DETAIL :
GRANT :
GRANT DETAIL :
USER CODE :

S	AUG 2017	ANNUAL BALANCE	ALL YEARS BALANCE
ESTIMATED REVENUES	.00	.00	.00
REVENUES	.00	.00	.00
UNREALIZED REVENUES	.00	.00	.00
BUDGET	.00	1,115,930.00	1,115,930.00
EXPENDITURES	43,361.60	445,532.80	445,532.80
ENCUMBRANCES	-46,836.60	633,658.38	633,658.38
PRE-ENCUMBRANCES	.00	.00	.00
REMAINING BALANCE	3,475.00	36,738.82	36,738.82

F1-HELP F2-SELECT F4-PRIOR F5-NEXT
F9-LINK F10-PRIOR-MO F11-NEXT-MO
G005 - PRIOR RECORD DISPLAYED