

**Public Works Engineering and Construction Management -  
Construction Bid Forecast**

**July, August, September 2025**

010622	Crosswater Blvd. Drainage Improvements	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Crosswater Boulevard Drainage Improvements. This project includes structural repairs to a deteriorated concrete box culvert and wing walls located within the Pablo Bay subdivision. Work involves post-tensioning, soil anchors, erosion control, and coordination with adjacent HOA infrastructure to maintain roadway integrity and prevent further degradation.
010396	Firestone Rd - Wheat Rd Intersection Improvements	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Firestone Road and Wheat Road Intersection Improvements. This project upgrades the existing four-way stop to a fully signalized intersection and includes milling, resurfacing, drainage enhancements, new lighting, and traffic signal installation. Coordination with JEA is also required for relocation of water and force mains, which will be funded separately by JEA.
010592	McCoy's Creek Branches	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of McCoy's Creek Branches. The work includes clearing and grubbing, channel excavation and significant environmental remediation. The project site consists of lands and banks surrounding McCoy's Creek from Beaver Street to Edison Avenue.

011034	Sedgemoore Drive Drainage Improvements	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Sedgemoore Drive Drainage Improvements. This project addresses severe roadway deterioration caused by a high water table through installation of a new underdrain system, curb and gutter replacement, and asphalt repairs along Sedgemoor and Halethorpe Drives. The improvements are part of the City's DSR program and support Jacksonville's Resilience Strategy.
October, November, December 2025		
010668	Cecil Mega Site Rail Spur	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of the Cecil Mega Site Rail Spur. The City's rail spur will connect a future development site to the CSX main line north of I-10. The approximately 1.5-mile spur will traverse beneath I-10 and across a JEA transmission easement before ultimately terminating adjacent to the future development. In addition to sub-ballast, ballast, railroad ties, and track, the project will also include mass clearing & grubbing and box culvert construction.
008814	Duval Road Sidewalk	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Duval Rd. Sidewalk. Work includes construction of a new sidewalk, pedestrian bridges and required drainage improvements along Duval Road from Biscayne Blvd. to Airport Rd. The project length is approximately 1 mile.

010984	Euclid Street Curb and Gutter	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Euclid Street Curb & Gutter. The intent of the project is to construct City Standard Curb & Gutter along one block of Euclid Street, between St. Johns Avenue and Woodmere Street. In addition to approximately 375 linear feet of curb & gutter, the project also includes milling & resurfacing and replacement of concrete driveways and walkways at the back of the proposed curb.
010143	Free Avenue Drainage Improvements	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Free Avenue Drainage Improvements. The project will install a new stormwater system to replace the current failing infrastructure. The project limits are from Galveston Ave to Hare Ave.
010377	Frye Ave. W. Drainage Improvements	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Frye Avenue West Drainage Improvements. The project will install a new stormwater system (380 feet of 18" RCP) to reduce flooding in the area.
010398	Lone Star Road Extension (Phase 2)	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of the Lone Star Road Extension (Phase 2). This phase extends Lone Star Road eastward with new stormwater systems, roadway construction, and pedestrian facilities. The project will also signalize the Mill Creek and Lone Star Road intersection to improve safety and traffic operations.

010991	Mallory St. Drainage Improvements	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Mallory Street Drainage Improvements. This project will upgrade aging storm drain infrastructure and mitigate ponding in low-lying areas along Mallory Street. The scope includes roadway improvements featuring porous asphalt pavement to enhance infiltration and long-term drainage performance.
001206	McCoy's Creek Greenway	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of McCoy's Creek Greenway. Work includes construction of a new shared use path, pedestrian bridges, boardwalks, park amenities, and landscaping along McCoy's Creek from Leland St. to Margaret St. The project length is approximately 1 mile.
010599	Oakleaf Village Parkway at Merchants Way Turn Lane	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of the Oakleaf Village Parkway Turn Lane. The project will add a new right turn lane and pavement markings from Merchants Way onto Oakleaf Village Parkway. Some drainage work is included.
008816	Ranch Road Sidewalk	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Ranch Road Sidewalk. Work includes construction of a new sidewalk and required drainage improvements along Ranch Road from Tradeport Drive to Duval Road. The project length is less than 0.25 miles and will likely be bid with the Duval Rd. Sidewalk project.

010385	Sheridan Street Drainage Improvement	Furnishing all labor, materials, and equipment; and performing all operations necessary for the construction of Sheridan Street Drainage System Rehabilitation. This project addresses failed stormwater infrastructure as part of the City's DSR program. It includes underdrain replacement, drainage structure upgrades, and surface restoration.
--------	--------------------------------------	--

**The information provided reflects planned activities and is subject to change. To discuss any project(s) with Public Works Staff, contact Donna Seetram Holder at SeetramD@coj.net or 904-255-8762 to schedule an appointment. Meetings must be held prior to the Procurement Solicitation Silence Period.**