SUBJECT: **DEMO & SITE CLEARANCE OF 44 PROPERTIES**

BID# CF-0053-17 OPEN DATE: **2016-12-07**

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT:
CONSTRUCTION FIXED

AGENCY: **MUNICIPAL CODE**

BASIS OF AWARD: **BY ITEM TO THE LOWEST RESPONSIVE, RESPONSIBLE BIDDER**

NUMBER OF BIDS INVITED 6 NUMBER RECEIVED 4 OTHER 0

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:

Item #8 was awarded to ERS Corp on 12/22/16 in the amount of $4,400.00 which included $275.00 cost of asbestos survey as required by bid specifications. The performed asbestos survey requires an asbestos abatement be performed prior to demolition. In accordance with the specifications, the awarded contractor solicited three quotes for asbestos abatement from the following companies:
1) Jensafe Environmental- $3,500.00; 2) ELS Abatement- $5,315.00 and; 3) Alachua Environmental Srvs- $6,800.00

Recommend approval to increase award for Item #8 to ERS Corp, in the amount of $3,500.00 for the asbestos abatement. Total award amount for Item #8 not-to-exceed $7,900.00.

This award to be funded by account: ERCD1N1FR-03410 to be executed by Purchase Order/Change Order.

Attachments: Recommendation, Change Order, Vendor Quotes, Asbestos Report, Previous Award

BUYER: Marilyn Laidler
MARILYN LAIDLER

RESPECTFULLY SUBMITTED: _____
GREGORY PEASE, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: **Bryan Mosier, Chief, Municipal Code Compliance Division**

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE
MEMBERS APPROVING _____ MEMBERS DISAPPROVING _____ DATE: _____

_____ _____ OTHER: _____

_____ _____

_____ _____

ACTION OF AWARDING AUTHORITY DATE: _____

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

FORM GB-108, Revised 12/2007

NEIGHBORHOODS DEPARTMENT

MUNICIPAL CODE COMPLIANCE DIVISION

Jacksonville
Where Florida Begins.

April 5, 2017

M E M O R A N D U M

TO: Gregory Pease, Division Chief
Procurement Division

FROM: Bryan Mosier, Division Chief
Municipal Code Compliance Division

RE: Change Order Request for Item #8 on Formal Demolition Bid #CF-0053-17

The survey of the condemned structure at 14060 Gossett St. revealed asbestos in the drywall system with popcorn finish in which a licensed asbestos abatement contractor must remove prior to demolition of this condemned structure.

I recommend approval of the change order request submitted by ERS Corp. in the amount of $3,500.00 (reference purchase order #7A05007).

Contractor	Item Number	Amount
ERS Corp.	8	$3,500.00

Funding Source: ERCD1N1FR /03410

BM/ds

ERS Corp.

PROPOSAL

Prepared for:
COJ- Municipal Code Compliance Division
Neighborhoods Department
214 N Hogan St., 7th Floor
Jacksonville, FL 32202

Proposal No: 17503_CO1
Date 3/31/2017
Phone: 904-255-7015
Fax: 904-255-8920
E-Mail: mchao@coj.net

Attention: Mr. Michael Chao

RE: 14060 Gossett Street RE: 0107666-0005 (Case No. 2016-30133)
Current Purchase Order No. PO7A05007

Request for Change Order#1:

Original Contract Amount.....$ 4,400.00

Asbestos Abatement of Ceiling Texture..... $ 3,500.00

We appreciate the opportunity to submit this proposal. If you have any questions or require additional information, please contact John Anderson.

Submitted by:
John Anderson
President – ERS Corp.

ENVIRONMENTAL

"Serving All Your Environmental Needs"

Ph: 904-695-1424
Fx: 904-695-1425

610-3 N. Lane Avenue
Jacksonville, FL 32254

March 24, 2017

ERS
760 Talleyrand Ave
Suite 200
Jacksonville, FL 32202
Email: j.anderson@ersfl.com

Attention: John Anderson
RE: Remove Sheetrock with Ceiling Texture at 14060 Gossett Street.

We are pleased to provide this quote for your consideration on the project as referenced above.

Scope of Work

- Mobilize all equipment and materials to site listed above.
- Remove and dispose approximately 1,100 S/F of sheetrock with ceiling texture.
- The wet method will be utilized for the removal of asbestos containing materials.
- All ACM debris will be disposed of at and approved landfill.
- Employees will use personal protective equipment.
- All work will be performed during normal working hours.

The total cost of this project will be Three Thousand Five Hundred Dollars ($3,500.00).

CLARIFICATIONS:

1. Our proposal includes two (2) million dollar, per occurrence, one million dollar umbrella, per aggregate liability insurance coverage.
2. Work to be completed under current Federal, State, and Local agency regulation, which includes the filing of all notification and permits. Permit fees will be an additional charge, if applicable.

3. Asbestos material removed from the job site will be disposed of in an EPA authorized landfill and the disposal receipt provided to the customer.
4. Customer to provide access for asbestos contractor's vehicles and equipment near the immediate work area.
5. Ten working day notification is required / is not required / will be determined by Duval County Regulatory and Environmental, Air Quality Division.
6. This proposal is based upon 1 mobilization to the project site.
7. Customer to provide water and electric to job site.
8. Customer the responsible for any items saved prior to Asbestos Abatement.
9. Not responsible for damages during abatement.

We appreciate the opportunity to provide this quote to you on this project and look forward to working with you. If you have any questions or require further assistance, please do not hesitate to call me at (904) 695-1424.

Sincerely,

_____ _____

Acceptance of Proposal Date

Eli Jensen

ELS Abatement & Construction, Inc.
1408 St. Johns Bluff Rd. N.
Jacksonville, FL 32225

March 21, 2017

Mr. John Anderson
ERS Corp.
760 Talleyrand Ave.
Jacksonville, Fl. 32202

Re: Asbestos Abatement at 14060 Gossett St. Jacksonville, FL.

PROPOSAL:

ELS is pleased to submit a proposal to perform the ceiling demolition of approximately 1,150 sq. ft. of the drywall system that contains friable ACM popcorn finish of the property listed above. The below is included.

- Labor, supplies and equipment
- Wet method
- 10 day Notification to FDEP
- In accordance with 29 CFR 1926.1101
- All asbestos contained materials will be disposed of at Trail Ridge Landfill via appropriate manifest

Price: **$ 5,315.00**

(Five thousand three hundred fifteen dollars and 00/100 cents)

Any alterations or deviations from above specification involving extra cost with be executed only upon written order, and will become an Extra charge over and above the estimate. All agreements contingent upon strikes, accidents or delays beyond our control.

Respectfully Submitted by: ELS Abatement & Construction, Inc.

Proposal Accepted by: _____ Date: _____

_____ Date: _____

ALACHUA ENVIRONMENTAL SERVICES, INC
[illegible]

** PROPOSAL **

DATE : March 29, 2017

ATTN : ERS
760 Talleyrand Avenue
Jacksonville, Florida 32202

TO : Mr. John Anderson

RE : ***RES. @ 14060 GOSSETT STREET***
JACKSONVILLE, FLORIDA

Alachua Environmental Services, Inc. propose to provide all labor and materials to conduct the removal and disposal of asbestos containing materials on the above referenced project. The following notations and exclusions shall clarify our quote.

REMOVE AND DISPOSE OF ASBESTOS CONTAINING DRYWALL WITH POPCORN FINISH. QUOTE BASED ON REGULAR WORKING HOURS. QUOTE DOES NOT INCLUDE ANY 3RD PARTY CONSULTANT OR MONITORING. A. E. S., INC. WILL COMPLY WITH ALL LOCAL, STATE AND FEDERAL REGULATIONS AND WILL DISPOSE OF ALL WASTE AT TRAIL RIDGE LANDFILL; JACKSONVILLE, FL. PER COJ REQUIREMENTS.

A. E. S., INC. WILL CONDUCT WORK FOR THE SUM OF: $6,800.00

Alachua Environmental Services, Inc. would like to thank you for this opportunity to quote this proposal with you. Should you have any questions regarding this proposal, please feel free to give me a call.
Cell contact # 904-334-1527 / Fax # 904-259-6299 Email @ [illegible]

Sincerely,
ALACHUA ENVIRONMENTAL SERVICES, INC.

Owen E. Thornton

OWEN E. THORNTON
President

OET / kc

[illegible]

ENVIRONEERING INC.
109 AZALEA POINT DRIVE SOUTH • PONTE VEDRA BEACH • FLORIDA • 32082

March 16, 2017

Mr. John Anderson, President
E. R. S. Corp
760 Talleyrand Avenue
Jacksonville, Florida 32202

Reference: One (1) Single Story Structure – Asbestos Demolition Survey – House
14060 Gossett Street
Jacksonville, Florida – JON 5930

Dear Mr. Anderson:

Pursuant to your request an Asbestos Demolition Survey has been performed at the above location for the purpose of identifying asbestos that needs to be removed prior to the planned demolition of the structure. The purpose of the investigation was to visually identify homogenous materials that need to have bulk samples obtained for analysis to determine the presence of Asbestos Containing Building Materials with in the structure. The scope of this survey was limited to the referenced one (1) single story structure in Jacksonville, Florida. The building was inspected for demolition. The facility has one single story structure for demolition, which is constructed with concrete, wood, popcorn, vinyl floor tile, drywall, steel and aluminum. There were six (6) suspected materials that were sampled for Polarized Light Microscopy (PLM) analysis. Based on the visual inspection, it was evident that National Emission Standard for Hazardous Air Pollutants (NESHAP) 40 CFR Part 61 regulated Asbestos Material was found to be present at the facility. The scope of work for this survey included sampling and analysis of suspect homogenous building materials. The asbestos demolition inspection process was initiated on March 11, 2017. Materials must contain greater than 1% asbestos to be regulated. The following recommendations are provided for the material that was found to contain Asbestos Fibers within the referenced structure.

RECOMMENDATIONS

Recommended response actions have been selected for all Asbestos Containing Materials identified by this survey within the facility. Recommendations for response actions, where arrived at, are stated as follows:

FRIABLE ASBESTOS CONTAINING MATERIALS

Friable Asbestos Material means any material containing more than one (1%) percent asbestos, that when dry can be crumbled, pulverized or reduced to powder by hand pressure.

(904) 665-0100 (904) 612-1456 • MOBILE (904) 665-0101 • FAX

Friable Asbestos Material was found in the following area:

HM-1 Drywall System with Popcorn Finish – White [2% Chrysotile Asbestos]

The above material is considered friable and must be removed by a Certified Florida Asbestos Abatement Contractor prior to any disturbance caused by renovation or demolition of the referenced structure.

CATEGORY I, NON-FRIABLE ASBESTOS MATERIAL

None.

CATEGORY II, NON-FRIABLE ASBESTOS MATERIAL

None.

NONREGULATED BY NESHAP; REGULATED BY OSHA

None.

The preceding materials are considered a Category I or II Non-Friable Material and therefore, under normal circumstances, the Category I material does not need not be removed prior to demolition, because generally these materials do not release significant amounts of Asbestos Fibers, even when damaged.

Category I material must be kept wet to prevent the release of fibers during demolition. The Category I asbestos waste must be placed in a permitted asbestos landfill in accordance with FDEP regulations. Friable asbestos and Category II material must be removed prior to demolition or renovation of the structure. Yet, in the event removal is deemed necessary as a part of renovation all Asbestos Containing Material should be removed by a Florida Licensed Asbestos Contractor. The building materials identified in this asbestos renovation survey were in good condition to significantly damaged at the time of the inspection. The material condition can change over time and will degrade with exposure to water, air movement, physical damage, weather and chemical exposure.

The structure has an address of, 14060 Gossett Street, Jacksonville, Florida. The facility was at one time a house. The facility has one single story structure for demolition.

When implementing the response actions, parties responsible for final selection should remember that actions shall be sufficient to protect HUMAN HEALTH AND THE ENVIRONMENT, but may also be the least burdensome method. Nothing in these recommendations should be construed as PROHIBITING or discouraging removal.

All parties shall comply with all applicable laws, ordinances, rules and regulations of Federal, State and Local Governments and Agencies relating to or affecting the proposed work in whole or in part when implementing any response action associated with the facility.

The following samples are recommended to be further analyzed by the point count method using a positive stop approach.

None.

This asbestos survey shall not be used as a design or specification for the removal of asbestos within the referenced structure.

RECOMMENDATIONS FOR ASBESTOS ABATEMENT: (14060 Gossett Street, Jacksonville, Florida)

The HM-1 asbestos Drywall System with Popcorn Finish – White material must be removed by an asbestos abatement contractor prior to demolition. This material is regulated by both of the following regulations: the Occupational Safety and Health Administration (OSHA) Construction Standard for Asbestos found in Title 29 Code of Federal Regulations (CFR) Part 1926.1101 and by the National Emission Standards for Hazardous Air Pollutants (NESHAP) Title 40 CFR Part 61.145.

It has been a pleasure working with you and I look forward to working with you once again in the future. I can be reached at (904) 665-0100 or mobile (904) 612-1456 if you should have any questions.

Respectfully submitted,

Timothy W. Rudolph

3-16-2017

Timothy W. Rudolph, P.E., L.A.C.
Licensed Asbestos Consultant AX 0000058
Asbestos Business License ZA0000243
< ERS CORP-ASBESTOS- SURVEY-JON-5930.doc>

M03620

ROUTINE **CHAIN OF CUSTODY FORM** **JON 5930**

ENVIRONEERING, INC., 109 Azalea Point Drive South, Ponte Vedra Beach, Florida 32082

To Laboratory: Dove Environmental Laboratory
8910 Miramar Parkway, Suite 200
Miramar, FL 33025

ROUTINE TAT

Customer Information		**Date:**	3/11/2017
Company Name:	ENVIRONEERING, INC.	**Phone:**	(904) 665-0100
Address:	109 Azalea Point Drive South	**Fax:**	(904) 665-0101
City, State, Zip:	Ponte Vedra Beach, FL 32082	**Project:**	E R S, CORP
Contact:	Mr. Tim Rudolph		14060 Gossett Street
			Jacksonville, Florida
HOUSE & SHED			<COC-DOVE-5930-1.XLS>

Sample #	Sample Type	Sample Location	COLOR/AREA	F/NF
1-1,2&3	BULK	Drywall System with Popcorn Finish	White/Ceiling	F
2-1	BULK	1'X1' Vinyl Floor Tile (VFT) Beige Self Adhesive (Kitchen) - Two Layers	Beige/Floor	NF
3-1	BULK	1'X1' Vinyl Floor Tile (VFT) Dark Brown - Self Adhesive (Bathroom) Three Layers Total	Brown/Floor	NF
4-1	BULK	Stucco - Exterior - Gray	Gray/Exterior Walls	NF

[redacted]

ENCLOSURE (1)
ENVIRONEERING, INC. Ltr Dtd 3/16/2017

ASBESTOS - PLM *** USE POSITIVE STOP METHOD ***

CHAIN OF CUSTODY **CHECK # 2925** Paid

Date/Time	Released by:	Date/Time	Released by:
3/11/2017- 18:00	Tim Rudolph		
	TIM RUDOLPH		

Rec By - D. Hosein
Date/Time - 3-14-17 / 12:00pm

c:\program files\Microsoft office\office\mervin\COC1

DOVE ENVIRONMENTAL CORP.
8910 MIRAMAR PARKWAY, SUITE 200 MIRAMAR FL 33025
Tel. (954) 374-9274 Fax: (954) 639-7426

ASBESTOS TEST REPORT

CLIENT : ENVIRONEERING, INC.
ADDRESS: 109 AZALEA POINT DRIVE., SOUTH
PONTE VEDRA BCH FL 32082
PROJECT: JON 5930/ERS. CORP
14060 GOSSETT STREET JACKSONVILLE, FL
CONSULT: TIM RUDOLPH

PAGE : 1
DATE : 03/15/17
SAMPLE ID : 0703620
NVLAP Lab Code: 102053-0

LAB NO. : 01
FRI/HOM : YES/NO LAYERS: 03
DESCRIPTION : DRYWALL SYSTEM WITH POPCORN FINISH
POPCORN MATERIAL=2% CHRY
ASBESTOS TYPE: 2% CHRYSOTILE
OTHER FIBERS : 18% CELLULOSE
NON FIBERS : 55% MINERALS
15% POLYSTYRENE-FOAM

SAMPLE NO.: 1-1
DATE OF ANALYSIS: 03/14/17
10% PAINT

LAB NO. : 02
FRI/HOM : YES/NO LAYERS: 03
DESCRIPTION : DRYWALL SYSTEM WITH POPCORN FINISH
POPCORN MATERIAL=2% CHRY
ASBESTOS TYPE: 2% CHRYSOTILE
OTHER FIBERS : 18% CELLULOSE
NON FIBERS : 55% MINERALS
15% POLYSTYRENE-FOAM

SAMPLE NO.: 1-2
DATE OF ANALYSIS: 03/14/17
10% PAINT

LAB NO. : 03
FRI/HOM : YES/NO LAYERS: 03
DESCRIPTION : DRYWALL SYSTEM WITH POPCORN FINISH
POPCORN MATERIAL=2% CHRY
ASBESTOS TYPE: 2% CHRYSOTILE
OTHER FIBERS : 18% CELLULOSE
NON FIBERS : 55% MINERALS
15% POLYSTYRENE-FOAM

SAMPLE NO.: 1-3
DATE OF ANALYSIS: 03/14/17
10% PAINT

Dove Environmental Corporation is solely responsible for analysis performed on sample content supplied by client and is NVLAP accredited for Method 40 CFR Pt. 736, App. E to Subpart E EPA/600/R-93/116. Measurement Uncertainty information is available by contacting the Laboratory. Laboratory Reports will be kept for a period of three (3) years electronically. Percentages are visually estimated. Point count performed at clients request only. Results relates only to item analyzed. This report should not be reproduced by client or anyone without written permision from Dove Environmental Corporation. All samples will be stored for a period of 1 month. The use of the term NVLAP does not constitute endorsement by NVLAP or any agency of the United States Government. Floor-Tile is non-homogeneous and results only reflect sample content.

Analyst 1

R. Pepe Ramnath, PhD
LABORATORY MANAGER

DOVE ENVIRONMENTAL CORP.
8910 MIRAMAR PARKWAY, SUITE 200 MIRAMAR FL 33025
Tel. (954) 374-9274 Fax: (954) 639-7426

ASBESTOS TEST REPORT

CLIENT : ENVIRONEERING, INC.
ADDRESS: 109 AZALEA POINT DRIVE., SOUTH
PONTE VEDRA BCH FL 32082
PROJECT: JON 5930/ERS. CORP
14060 GOSSETT STREET JACKSONVILLE, FL
CONSULT: TIM RUDOLPH

PAGE : 2
DATE : 03/15/17
SAMPLE ID : D703620
NVLAP Lab Code: 102053-0

LAB NO. : 04 — SAMPLE NO.: 2-1
FRI/HOM : NO/NO LAYERS: 03 — DATE OF ANALYSIS: 03/14/17
DESCRIPTION : 1X1 VFT BEIGE SELF ADHESIVE
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 2% CELLULOSE
NON FIBERS : 58% MINERALS — 10% RESINS
30% POLYMERS

LAB NO. : 05 — SAMPLE NO.: 3-1
FRI/HOM : NO/NO LAYERS: 02 — DATE OF ANALYSIS: 03/14/17
DESCRIPTION : 1'X1' VFT DARK BROWN-SELF ADHESIVE
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 2% CELLULOSE
NON FIBERS : 58% MINERALS — 10% RESINS
30% POLYMERS

LAB NO. : 06 — SAMPLE NO.: 4-1
FRI/HOM : NO/NO LAYERS: 02 — DATE OF ANALYSIS: 03/14/17
DESCRIPTION : STUCCO-EXTERIOR-GRAY
ASBESTOS TYPE: NONE-DETECTED
OTHER FIBERS : 2% CELLULOSE
NON FIBERS : 58% MINERALS — 10% PAINT
30% POLYMERS

Dove Environmental Corporation is solely responsible for analysis performed on sample content supplied by client and is NVLAP accredited for Method 40 CFR Pt. 736, App. E to Subpart E EPA/600/R-93/116. Measurement Uncertainty information is available by contacting the Laboratory. Laboratory Reports will be kept for a period of three (3) years electronically. Percentages are visually estimated. Point count performed at clients request only. Results relates only to item analyzed. This report should not be reproduced by client or anyone without written permision from Dove Environmental Corporation. All samples will be stored for a period of 1 month. The use of the term NVLAP does not constitute endorsement by NVLAP or any agency of the United States Government. Floor-Tile is non-homogeneous and results only reflect sample content.

Analyst 1

R. Pepe Rammath, PhD
LABORATORY MANAGER

TITLE: DEMO & SITE CLEARANCE OF 44 PROPERTIES

BID NO.: CF-0053-17 (MUNICIPAL CODE)

OPEN DATE: DECEMBER 7 2016 @ 2PM

BUYER: MARILYN LAIDLER, PURCHASING ANALYST

No. Invited (6) No. Received (4) No Bid (0)

		P & G LAND CLEARING, INC.				ENVIRONMENTAL REMEDIATION				ARWOOD WASTE, INC.			
ITEM	DESCRIPTION	ASBESTOS SURVEY	ASBESTOS FREE DEMO	EXTENDED TOTAL	WET DEMOLITION	ASBESTOS SURVEY	ASBESTOS FREE DEMO	EXTENDED TOTAL	WET DEMOLITION	ASBESTOS SURVEY	ASBESTOS FREE DEMO	EXTENDED TOTAL	WET DEMOLITION
1	**2303 BELVEDERE STREET**, (MOBILE HOME & ACCESSORY) DESCRIBED AS: 10-22-40-1S-26E RIO VISTA LOTS 23, 24 BLK 57(DEMOLITION AND SITE CLEARANCE) R.E. #036529-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTH)	$ 275.00	$ 6,100.00	$ 6,375.00	$ 3,000.00	$ 275.00	$ 2,804.40	$ 3,079.40	$ 4,075.40	$ 350.00	$ 5,200.00	$ 5,550.00	$ 19,500.00
2	**1816 BRACKLAND STREET** (SINGLE FAMILY) DESCRIBED AS; 6-95 08-2S-27E R/P OF GLEN MYRA LOT 4 BLK 5 (DEMOLITION AND SITE CLEARANCE) R.E. #115687-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND A WET DEMOLITION) (URBAN CORE)	$ 275.00	$ 6,575.00	$ 6,850.00	$ 3,000.00	$ 275.00	$ 4,375.00	$ 4,650.00	$ 5,650.00	$ 450.00	$ 7,050.00	$ 7,500.00	$ 24,900.00
3	**7504 CALVIN STREET**, (SINGLE FAMILY) DESCRIBED AS: 8-31 39-1S-26E .32 HESELTON S/D N 100FT OF S 119FT OF 140FT LOT 28 (DEMOLITION AND SITE CLEARANCE) R.E. #026718-0200 (CONTRACTOR MUST SUBMIT A BID FOR COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTH)	$ 475.00	$ 14,775.00	$ 15,250.00	$ 5,000.00	$ 275.00	$ 5,895.00	$ 6,170.00	$ 7,170.00	$ 450.00	$ 7,500.00	$ 7,950.00	$ 28,500.00
4	**1719 CLYDE STREET** (SINGLE FAMILY) DESCRIBED AS; 13-27 40-1S-26E RIVERVIEW ESTATES LOTS 13,14 BLK 144 (DEMOLITION AND SITE CLEARANCE) R.E. #037053-0000 (CONTRACTOR MUST SUBMIT A BID FOR COST OF AN ASBESTOS SURVEY AND WET DEMOLITON) (NORTH)	$ 275.00	$ 3,875.00	$ 4,150.00	$ 3,000.00	$ 275.00	$ 4,612.50	$ 4,887.50	$ 5,887.50	N/A	N/A	N/A	N/A
5	**1435 DYAL STREET**, (SINGLE FAMILY) DESCRIBED AS; 5-3 08-2S-27E .207 TENTH STREET RIDGE S/D LOT 14, W 23.75FT LOT 15, E 1/2 LOT 13 (DEMOLITION AND SITE CLEARANCE) R.E. #115368-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (URBAN CORE)	$ 275.00	$ 5,275.00	$ 5,550.00	$ 3,000.00	$ 275.00	$ 2,820.00	$ 3,095.00	$ 4,095.00	$ 450.00	$ 5,500.00	$ 5,950.00	$ 24,900.00
6	**1187 S EDGEWOOD AVENUE**, (SINGLE FAMILY & ACCESSORY) DESCRIBED AS:5-86 21-2S-26E MURRAY HILL HEIGHTS NW 80 LOT 1 BLK 45 (DEMOLITION AND SITE CLEARANCE) R.E. #061487-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTHWEST)	$ 600.00	$ 27,500.00	$ 28,100.00	$ 10,000.00	$ 1,000.00	$ 25,916.40	$ 26,916.40	$ 27,916.40	$ 650.00	$ 34,900.00	$ 35,550.00	$ 105,000.00
7	**2104 EVERGREEN AVENUE**, (SINGLE FAMILY & ACCESSORY) DESCRIBED AS: 2-55 07-2S-27E .126 RICHARDSON S/D N 1/2 OF NW 1/4 E 104 FT LOT 75 (DEMOLITION AND SITE CLEARANCE) R.E. #115064-0000(CONTRACTOR MUST SUBMIT A BID FOR THE COST OF ASBESTOS SURVEY AND A WET DEMOLITION) (URBAN CORE)	$ 375.00	$ 5,975.00	$ 6,350.00	$ 3,000.00	$ 275.00	$ 3,695.00	$ 3,970.00	$ 4,970.00	$ 450.00	$ 6,800.00	$ 7,250.00	$ 23,900.00
8	**14060 GOSSETT STREET**, (SINGLE FAMILY) DESCRIBED AS: 6-9 37-1N-27E .24 DUVAL CITY LOT 25 BLK 4 (DEMOLITION AND SITE CLEARANCE) R.E. #107666-0005 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTH)	$ 275.00	$ 5,275.00	$ 5,550.00	$ 3,000.00	$ 275.00	$ 4,125.00	$ 4,400.00	$ 5,400.00	$ 450.00	$ 6,900.00	$ 7,350.00	$ 25,900.00
9	**1887 HARDEE STREET**, (SINGLE FAMILY) DESCRIBED AS; 4-1 10-2S-26E .172 COLLEGE PARK LOTS 12,13 BLK 18 (DEMOLITION AND SITE CLEARANCE) R.E. #050864-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITON) (NORTHWEST)	$ 275.00	$ 4,250.00	$ 4,525.00	$ 2,000.00	$ 275.00	$ 2,637.50	$ 2,912.50	$ 3,192.50	$ 350.00	$ 5,400.00	$ 5,750.00	$ 23,500.00
10	**11545 HOLTON LANE** (MOBILE HOME) DESCRIBED AS; 02-1S-25E 1.37 PT GOVT LOT 3 RECD O/R 9757-2090 (DEMOLITION AND SITE CLEARANCE) R.E. #002588-0600 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTH)	$ 275.00	$ 14,775.00	$ 15,050.00	$ 5,000.00	$ 275.00	$ 3,000.00	$ 3,275.00	$ 4,275.00	N/A	N/A	N/A	N/A
11	**3064 JENNINGS ROAD**, (MOBILE HOME & ACCESSORY) DESCRIBED AS; 5-74 04-1S-26E GARDEN CITY S/D NE 1/4 OF SE 1/4 LOTS, 1,2 PT CLOSED ST BLK 6 O/R BK 4862-787 (DEMOLITION AND SITE CLEARANCE) R.E. #019779-0000 (CONTRACTOR MUST SUBMIT A BID FOR THE COST OF AN ASBESTOS SURVEY AND WET DEMOLITION) (NORTH)	$ 275.00	$ 4,975.00	$ 5,250.00	$ 3,000.00	$ 275.00	$ 2,263.20	$ 2,538.20	$ 3,538.20	$ 350.00	$ 5,500.00	$ 5,850.00	$ 22,900.00

SUBJECT: **DEMO & SITE CLEARANCE OF 44 PROPERTIES**

BID# CF-0053-17 OPEN DATE: **2016-12-07**

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT:
CONSTRUCTION FIXED

AGENCY: **MUNICIPAL CODE**

BASIS OF AWARD: **BY ITEM TO THE LOWEST RESPONSIVE, RESPONSIBLE BIDDER**

NUMBER OF BIDS INVITED 6 NUMBER RECEIVED 4 OTHER 0

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:

Recommend approval of award to the lowest responsive, responsible bidder(s) as follows: Environmental Remediation, bid item(s): 1, 2, 3, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 17, 18, 19, 20, 21, 22, 24, 25, 26, 27, 28, 29, 30, 31, 32, 34, 38, 39, 41, 42 and 43 in the amount of $165,583.89; P & G Land Clearing, Inc., bid item(s), 4, 23, 33, 35, 36, 37, 40 and 44 in the amount of $37,200.00. Total award amount not-to-exceed $202,783.89.

Item 16 will not be awarded at this time.

This award to be funded by account: ERCD1N1FR-03410 to be executed by Purchase Order(s).

Attachments: Recommendation Memo, Bid Tabulation Sheet, Terms & Conditions

BUYER: Marilyn Laidler
MARILYN LAIDLER

RESPECTFULLY SUBMITTED: Greg Pease
GREGORY PEASE, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: **Bryan Mosier, Chief, Municipal Code Compliance Division**

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)

ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING 3 MEMBERS DISAPPROVING Ø DATE: 12/22/16

Teresa R. Eilbeck OTHER:

ACTION OF AWARDING AUTHORITY DATE: 12/22/16

APPROVED ✓ DISAPPROVED

OTHER

SIGNATURE OF AUTHENTICATION Sam E. Mousa

Sam E. Mousa
Chief Administrative Officer
For: Mayor Lenny Curry
Under Authority of:
Executive Order No. 2015-05
FORM GB-108, Revised 12/2007

QWS3270X 4/7/2017 2:11 PM
FAML6350 V5.1 ** NW COJ FAMIS PRODUCTION ** 04/07/2017
LINK TO: ACCOUNT SUMMARY INQUIRY 2:11 PM

FISCAL MO/YEAR : 07 2017 CURRENCY CODE :
INDEX CODE : ERCD1N1FR FORECLOSED PROPERTY REGISTRY-HOUSING SER
SUBOBJECT : 03410 CONTRACTUAL SERVICES
PROJECT :
PROJECT DETAIL :
GRANT :
GRANT DETAIL :
USER CODE :

S	APR 2017	ANNUAL BALANCE	ALL YEARS BALANCE
ESTIMATED REVENUES	.00	.00	.00
REVENUES	.00	.00	.00
UNREALIZED REVENUES	.00	.00	.00
BUDGET	.00	1,115,930.00	1,115,930.00
EXPENDITURES	18,425.00	98,804.00	98,804.00
ENCUMBRANCES	-18,425.00	310,767.20	310,767.20
PRE-ENCUMBRANCES	.00	.00	.00
REMAINING BALANCE	.00	706,358.80	706,358.80

F1-HELP F2-SELECT F4-PRIOR F5-NEXT
F9-LINK F10-PRIOR-MO F11-NEXT-MO
G005 - PRIOR RECORD DISPLAYED