15

SUBJECT: BISCAYNE BOULEVARD BRIDGE OVER I-295

BID #: CF-0151-21

OPEN DATE: 2021-11-03

GENERAL GOVERNMENT AWARDS COMMITTEE

KIND AND BASIS OF CONTRACT: CONSTRUCTION FIXED- ENCOURAGEMENT

AGENCY: PUBLIC WORKS

BASIS OF AWARD: TOTAL BASE BID, PLUS SELECTED ALTERNATES (IF ANY)-LOWEST RESPONSIVE, RESPONSIBLE BIDDER

NUMBER OF BIDS INVITED: 9 **NUMBER RECEIVED: 1** **OTHER: 1**

SUMMARY OF BIDS AND RECOMMENDED ACTIONS:
Recommend approval of award to Superior Construction Company Southeast, LLC as the only responsive, responsible bidder for the Biscayne Boulevard Bridge Over I-295 project. Total award amount not to exceed $1,897,601.40.

Funding for this award shall be encumbered from 001334.565051.3.32111.384020. To be executed by formal contract through the Office of General Counsel.

ATTACHMENTS: Recommendation Memo, Bid Tabulation, Basis of Award, Scope of Work

ANALYST: _____
BRYAN MATUS

RESPECTFULLY SUBMITTED: _____
GREGORY PEASE, CHIEF
PROCUREMENT DIVISION

CONCURRENCE BY: Robin G. Smith P.E., Chief, Engineering & Construction Management

---

(ALL AWARD ACTIONS SUBJECT TO LAWFULLY APPROPRIATED FUNDS)
ACTION OF GGAC COMMITTEE ON RECOMMENDATIONS ABOVE

MEMBERS APPROVING _____ MEMBERS DISAPPROVING _____ DATE: _____

_____ _____ OTHER: _____

_____ _____

_____ _____

ACTION OF AWARDING AUTHORITY DATE _____

APPROVED _____ DISAPPROVED _____

OTHER _____

SIGNATURE OF AUTHENTICATION _____

City of Jacksonville, Florida

Lenny Curry, Mayor

Department of Public Works
214 N. Hogan St., 10th floor
Jacksonville, FL 32202
(904) 255-8786
www.coj.net

ONE CITY. ONE JACKSONVILLE

November 9, 2021

TO: Gregory W. Pease
Chief of Procurement

THRU: John P. Pappas, P.E.
Director

FROM: Robin G. Smith, P. E.
Chief, Engineering & Construction Management

SUBJECT: RECOMMENDATION TO AWARD

RE: Biscayne Blvd. Sidewalk Over I-295 Bridge Modifications

Bid No.:	CF-0151-21
Bid Date:	November 3, 2021
Award Amount:	$1,897,601.40
Internal Services Account No.	PWEN011AD

The Department of Public Works has tabulated and reviewed the one (1) bid received for the referenced project for accuracy and compliance with the contract documents. Given the current bidding climate and the fact that we have seen steadily and rapidly increasing bid prices, we believe we have received a fair and reasonable bid from Superior Construction Company, Inc. This project was bid as encouragement. In addition, Public Works has confirmed through www.myfloridalicense.com the appropriate licenses for this contractor and listed subcontractors, if applicable.

Accordingly, we recommend that the Bid for Biscayne Blvd. Sidewalk Over I-295 Bridge Modifications be awarded to Superior Construction Company, Inc., 7072 Business Park Blvd., N., Jacksonville, Florida 32256, in accordance with the attached bid documents in the amount of $1,897,601.40.

Funding for this project should be encumbered as follows:

ACCOUNTS:	TOTAL
001334	
PWCP Public Works Capt'l Proj-Oth Trans Svcs	
565051	
3	
32111-384020	
$1,897,601.40	$1,897,601.40

RGS/lw

Attachments

cc: Lori West, Engineering and Construction Management
Richard Cooper, Engineering and Construction Management
David D. Hahn, P.E. Engineering and Construction Management

BID TABULATION

Title:	Biscayne Boulevard Sidewalk Over I-295 Bridge Modifications
Bid No:	CF-0151-21
Open Date:	November 3, 2021
Analyst:	Bryan Matus
No. Invited:	(9) No. Received: (1) Other: (1)
Recorded By:	John Hernandez

Item #	FDOT Pay Item No. *	Special Conditions	Description	Qty.	Unit	Superior Construction Company Southeast, LLC Unit Price	Extended Price
			Roadway				
1		31.16	As Built Drawings	1	LS	$15,000.00	$15,000.00
2		31.7	Erosion Control and Pollution Abatement	1	LS	$21,000.00	$21,000.00
3		31.8	Mobilization	1	LS	$189,000.00	$189,000.00
4		31.9	Site Preparation	1	LS	$274,500.00	$274,500.00
5		31.10	Maintenance of Traffic	1	LS	$227,500.00	$227,500.00
6		31.12.1	Regular Excavation and Fill	1	LS	$18,000.00	$18,000.00
7	102-14	31.46	Traffic Control Officer	896	HR	$66.00	$59,136.00
8	102-60	31.22	Work Zone Signs	10310	ED	$0.22	$2,268.20
9	102-71-15	31.23	Temporary Barrier, F&I, Anchored	328	LF	$49.00	$16,072.00
10	102-71-16	31.24	Temporary Barrier, F&I, Free Standing	264	LF	$32.00	$8,448.00
11	102-74-1	31.25	Channelizing Device, - Types I, II, DI, VP,Drum, or LCD	3960	ED	$0.12	$475.20
12	102-76	31.26	Arrow Board / Advance Warnning Arrow Panel	60	ED	$6.00	$360.00
13	102-89-1	31.27	Temporary Crash Cushion	2	LO	$2,600.00	$5,200.00
14	102-99	31.28	Portable Changeable Message Sign - Temporary	90	ED	$11.00	$990.00
15	102-115	31.47	Type III Barricades	270	ED	$5.00	$1,350.00
16	102-120	31.48	Temporary Traffic Signal, Portable	400	ED	$65.00	$26,000.00
17	102-150-1	31.48	Portable Regulatory Sign	120	ED	$5.00	$600.00
18	102-150-2	31.49	Radar Speed Display Unit	120	ED	$5.00	$600.00
19	102-913-21	31.29	Removable Tape Pavement Marking - White / Black - Solid	0.338	GM	$16,000.00	$5,408.00
20	102-913-31	31.30	Removable Tape Pavement Marking - Yellow - Solid	0.265	GM	$16,000.00	$4,240.00
21	430-175-115	31.19.2	15" RCP Pipe	8	LF	$1,740.00	$13,920.00
22	425-1-705	31.19.3	Inlets, Gutter, Type S, Partial (Furnish andInstall)	2	EA	$3,590.00	$7,180.00
23	425-1-881	31.19.3	Curb and Gutter Barrier Wall Inlet (Furnishand Install)	2	EA	$5,535.00	$11,070.00
24		31.19.3	COJ Storm Sewer Inlet Grate and Frame(Furnish and Install)	2	EA	$1,800.00	$3,600.00
25	339-1	31.33	Miscellaneous Asphalt Pavement	12	TN	$670.00	$8,040.00
26	515-1-1	31.51	Pipe Handrail - Guiderail (Steel)	164	LF	$118.00	$19,352.00
27	521-72-40	31.38	Shoulder Concrete Barrier	44	LF	$630.00	$27,720.00
28	536-1-0	31.35	Guardrail (TL-2)	200	LF	$31.00	$6,200.00
29	536-8-12	31.36	Guardrail Approach Transition Connection toRigid Barrier (TL-2)	2	EA	$2,275.00	$4,550.00
30	536-6	31.37	Pipe Rail for Guardrail	200	LF	$25.25	$5,050.00

BID TABULATION

Title:	Biscayne Boulevard Sidewalk Over I-295 Bridge Modifications					**Superior Construction Company Southeast, LLC**	
Bid No:	CF-0151-21						
Open Date:	November 3, 2021						
Analyst:	Bryan Matus						
No. Invited:	(9) **No. Received:** (1) **Other:** (1)						
Recorded By:	John Hernandez						
Item #	**FDOT Pay Item No. ***	**Special Conditions**	**Description**	**Qty.**	**Unit**	**Unit Price**	**Extended Price**
31	536-85-24	31.37	Guardrail End Treatment, Parallel ApproachTerminal	2	EA	$2,995.00	$5,990.00
32	710-90	31.20.3	Painted Pavement Markings - Final Surface	1	LS	$3,500.00	$3,500.00
33	711-16-221	31.20.3	Thermoplastic, Std, White, Solid, 6"	1160	LF	$1.20	$1,392.00
34			Concrete Sidewalk, 4"	165	SY	$115.00	$18,975.00
35	711-16-224	31.20.3	Thermoplastic, Std, Yellow, Solid, 18"	22	LF	$10.00	$220.00
36		31.20.3	Thermoplastic, Std, Yellow, Solid, 18"			$0.00	$0.00
37	713-103-101	31.20.3	Permanent Tape, White, Solid, 6" forConcrete Bridges	0.114	GM	$30,000.00	$3,420.00
38	713-103-201	31.20.3	Permanent Tape, Yellow, Solid, 6" forConcrete Bridges	0.114	GM	$30,000.00	$3,420.00
39		31.21	Sod	1740	SY	$5.00	$8,700.00
					Roadway Sub-Total (Items 1 - 39):	$	1,028,446.40
			Bridge				
40	110-3-1	31.39	Removal of Existing Bridge Deck	2942	SF	$95.00	$279,490.00
41	110-3-6	31.40	Removal of Existing Bridge Concrete TrafficBarrier	302	LF	$180.00	$54,360.00
42	400-2-4	31.41	Class II Concrete (Superstructure)	73	CY	$4,000.00	$292,000.00
43	415-1-4	31.42	Reinforcing Steel - Bridge Superstructure	18880	LB	$2.00	$37,760.00
44	521-5-13	31.43	Concrete Traffic Railing, Bridge, 36" Single -Slope	302	LF	$170.00	$51,340.00
45	521-6-11	31.44	Concrete Parapet, Pedestrian/Bicycle, 27"Height	302	LF	$240.00	$72,480.00
46	550-10-325	31.45	Fencing, Type R, 5.1-6.0', Vertical	302	LF	$245.00	$73,990.00
47	400-7	31.51	Bridge Deck Grooving, Less than 8.5"	85	SY	$91.00	$7,735.00
					Bridge Sub-Total (Items 40 - 47):	$869,155.00	
					Total (Items 1 - 47):	$1,897,601.40	
					Conflict of Interest	Yes	
					Licensed Sub	Self Perform	
					Bid Bond	Yes	
					Addendum 1-4	Yes	

B. BASIS OF AWARD

The project may be awarded to the lowest responsive, responsible Bidder. The Total Base Bid will be used to determine the lowest bidder, contingent on the availability of funds within the project's approved budget. The Total Base Bid plus selected Alternate(s), if any, will be used to determine the lowest bidder. If selected, Alternate(s) will be awarded in the order listed (i.e. - 1,2,3…). The CITY has the right to reject any or all bids.

C. REVISIONS OF BID PROPOSAL FORM

Request for revision of the Bid Proposal Form must be made to the ENGINEER at least three (3) days prior to date of opening of Bids. Revision of the Bid Proposal by the Bidder will void the Bid.

D. CONTRACT EXPIRATION DATE

The Contract expiration date shall be established as follows:

The notice to proceed date plus ten (10) calendar days for mobilization, plus the construction time established in the Proposal, plus time extensions pursuant to valid change orders (which shall establish the construction completion date), plus 120 days to assure a contract exists beyond the scheduled construction completion date in order to comply with Executive Order Number 13-05.

E. BID CHANGES

No changes in the amount of Bids appearing on the outside of Bids will be considered. Only the amounts shown on bidding documents inside the envelope will be considered. All changes, corrections and erasures must be initialed by the person signing the bid.

F. CONSTRUCTION COMPLETION

The CONTRACTOR shall begin work within ten (10) calendar days, including Sundays and holidays, after the date of written notice from the owner to begin work, and shall complete the Base Bid work within **200** calendar days including Sundays and holidays, after the expiration of such ten (10) day notice. If the Bidder determines that "off-hours" work is anticipated to complete the project within such allotted times, a schedule therefore shall be attached to this proposal as required by Section 20.3.4 of the General Conditions.

G. BID SECURITY

If Bid Security is required for this project, a Certified Check on _____ (or) Cashier's Check on _____ (or) Bid Bond properly executed by the undersigned and by qualified surety in the sum of _____ representing not less than five percent (5%) of the total amount of Bid, made payable to the Tax Collector, City of Jacksonville, Florida, which the undersigned Bidder hereby deposits as a guarantee of good faith and which it agrees to forfeit to the CITY of Jacksonville, not as a penalty, but as fixed and liquidated damages in the event it fails to enter into Contract, or fail to

BISCAYNE BOULEVARD SIDEWALK OVER I-295
BRIDGE MODIFICATIONS
SECTION 30

SCOPE OF WORK

30.1 Scope:

The work covered by these plans and specifications consists of furnishing all labor, materials and equipment; and performing all operations necessary for the construction of BISCAYNE BOULEVARD SIDEWALK OVER I-295 - BRIDGE MODIFICATIONS as specified in the Contract Documents. This includes the installation of all asphalt and roadway work, all concrete sidewalk work, all bridge work and all drainage pipes and drainage structures as shown in the construction plans.

30.2 Location:

This project is located within the limits of the City of Jacksonville, Florida. The proposed sidewalk's construction area is on Biscayne Boulevard at the I-295 Overpass Bridge.

30.3 Intent:

It is the intent of these Contract Documents to construct the project as shown on the plans and specifications. It is not the intent of these Contract Documents to minutely define the mode and fabric of construction of this project, but rather to set forth reasonable and rational criteria for the construction thereof.